

PROJECT NO. 0331

April 30, 2007

ADDENDUM NO. 3

**FIRE STATION 10/22
BIRMINGHAM, ALABAMA**

BIDS RECEIVED:

**2:00 p.m.
May 8, 2007
City Hall Room 410**

**ARCHITECTURAL DIVISION
DEPT. OF PLANNING, ENG. & PERMITS
WILLIAM A. GILCHRIST DIRECTOR
PAUL L. JENNINGS, AIA, CITY ARCHITECT**

THIS ADDENDUM IS DIRECTED TO ALL PRIME BIDDERS, AND ALL OTHERS TO WHOM DRAWINGS AND SPECIFICATIONS HAVE BEEN ISSUED.

THIS ADDENDUM FORMS A PART OF THE CONTRACT DOCUMENTS. THE FOLLOWING CONDITIONS TAKE PRECEDENCE OVER ANY CONFLICTING CONDITIONS IN THE DRAWINGS AND SPECIFICATIONS. THE DRAWINGS AND SPECIFICATIONS ARE HEREBY AMENDED IN THE FOLLOWING PARTICULARS.

SPECIFICATIONS

1. The bid date for this project has been postponed to May 8, 2007 at 2:00 PM.
2. Section 10350 Flag Pole – Morgan-Francis Flagpoles is as approve equal.
3. Section 16721 Fire Alarm System – Simplex is an approved equal.
4. Section 08710 Finish Hardware – Door 134 should be listed in Hardware Set 2.
5. Section 08360 Overhead Doors – Add requirement for Rolling Counter Fire Door at window DD. This door shall be 1 1/2 hour rated as manufactured by Cornell, Overhead Door, Raynor or approved equal.

DRAWINGS

1. Sheet P-1 – Gas Water Heater Schedule. For GWH-1 and GWH-2 add Bradford-White model PDY as an approved equal. Water storage capacity and fuel loads shall match those listed in the schedule for both water heaters.
2. Sheet M-1 Exhaust Fan Schedule, Exhaust Fan EF-2 – Change horsepower of the fan to 7 1/2.
3. Sheet E-7, Panel P2, circuit 32, 34, 36 for exhaust fan EF-2 – Change breaker to 50/3, wire to #6 in a 1" conduit.

CLARIFICATIONS

The top of wall elevation for the retaining wall shall be 688.5 at the west parking and shall vary from 681.0 at the 5th Avenue end to 686.0 at the alley end of the wall at the east parking. The east wall shall be stepped as needed to maintain a minimum top of wall 3'-0" above the parking level.

Sheet 2 of 2