ITEM DESCRIPTION:	PURCHASED	RECEIVED	INSTALLED	FINAL CONNECTION	CONTACT
ALARM SYSTEMS	OWNER	CONTRACTOR	OWNER	OWNER	
CABINETS, WOOD SHELVING, WOOD DOORS, ETC. (SEE SHEET A5)	OWNER	CONTRACTOR	CONTRACTOR		NOTES
CARBONATION	OWNER	CONTRACTOR	OWNER	OWNER	
CARPET, WALK-OFF CARPET, AND ADHESIVES	OWNER	CONTRACTOR	CONTRACTOR		
CEILING TILE	CONTRACTOR	CONTRACTOR	CONTRACTOR		
CHAIRS & BAR STOOLS	OWNER	CONTRACTOR	CONTRACTOR		
COFFEE & TEA MACHINES	OWNER	CONTRACTOR	CONTRACTOR	OWNER	
CONDENSER STAND FOR WALK-IN COOLER/FREEZER CONDENSER	OWNER	CONTRACTOR	CONTRACTOR		
CURVED COOPER CEILING	OWNER	CONTRACTOR	CONTRACTOR		NOTES
CUSTOM HARDWARE	OWNER	CONTRACTOR	CONTRACTOR		
DECORATIVE MIRRORS IN PUBLIC RESTROOMS	OWNER	CONTRACTOR	CONTRACTOR		
DECORATIVE STEER HORNS	OWNER	OWNER	OWNER		
DISH MACHINE	OWNER	CONTRACTOR	OWNER	CONTRACTOR	
DOORS & FRAMES 1 AND 2	CONTRACTOR	CONTRACTOR	CONTRACTOR		
ELECTRIC PANELS	CONTRACTOR	CONTRACTOR	CONTRACTOR	CONTRACTOR	
ENTRANCE MAT	OWNER	CONTRACTOR	CONTRACTOR		
EQUIPMENT GAS HOSES & REFRIGERANT CABLES	OWNER	CONTRACTOR	CONTRACTOR	CONTRACTOR	NOTES
EXHAUST FANS EF-1, EF-2, EF-3, & EF-4 MAKE-UP AIR UNIT	OWNER	CONTRACTOR	CONTRACTOR	CONTRACTOR	
EXTERIOR SEATING BENCHES	OWNER	OWNER	OWNER		
FIRE EXTINGUISHERS	CONTRACTOR	CONTRACTOR	CONTRACTOR		
GRATE COVER UNDER ICE MACHINE	OWNER	CONTRACTOR	CONTRACTOR		
GREASE CONTAINMENT BOXES	OWNER	OWNER	OWNER		
HOSTESS STAND	OWNER	CONTRACTOR	OWNER		
HVAC TEST & BALANCE	OWNER	OWNER	OWNER		
INDOOR TELEPHONE WIRES & SYSTEM	OWNER	CONTRACTOR	OWNER	OWNER	
KITCHEN EQUIPMENT	OWNER	OWNER	OWNER	CONTRACTOR	
KITCHEN EXHAUST HOODS AND HOOD FIRE SUPPRESSION SYSTEM AUTOMATIC GAS SHUT-OFF VALVE	OWNER	CONTRACTOR	CONTRACTOR	CONTRACTOR	NOTES
OFFICE FURNITURE	OWNER	OWNER	OWNER		
OUTDOOR TELEPHONE LINES	OWNER	CONTRACTOR	OWNER	OWNER	
PAGER HOLDER	OWNER	CONTRACTOR	CONTRACTOR		
PAPER TOWEL DISPENSERS	CONTRACTOR	CONTRACTOR	CONTRACTOR		
PARKING BUMPERS (CURB, STOPS)	CONTRACTOR	CONTRACTOR	CONTRACTOR		NOTES
PARKING LOT LIGHT FIXTURES & POLES, CHANDELIERS, EXTERIOR BUILDING FIXTURES, BUILDING INTERIOR FIXTURES, AND LAMPS	OWNER	CONTRACTOR	CONTRACTOR	CONTRACTOR	
POINT OF SALE SYSTEM	OWNER	OWNER	OWNER	OWNER	
ROOF TOP AIR CONDITIONING UNITS	OWNER	CONTRACTOR	CONTRACTOR	CONTRACTOR	NOTES
ROOFTOP REFRIGERATION EQUIPMENT	OWNER	CONTRACTOR	OWNER	CONTRACTOR	
SAFE	OWNER	CONTRACTOR	CONTRACTOR	CONTRACTOR	
SERVICE AREA PAPER TOWEL DISPENSER	OWNER	CONTRACTOR	CONTRACTOR		
SIGNS & LED - INTERIOR AND EXTERIOR	OWNER	CONTRACTOR	OWNER	CONTRACTOR	
SIGNS - PROJECT (MARKING)	OWNER	CONTRACTOR	CONTRACTOR		
SIGNS - ROAD	OWNER	CONTRACTOR	CONTRACTOR	CONTRACTOR	
STAINLESS STEEL BARS ON WALK-IN COOLER/FREEZER	OWNER	OWNER	OWNER		
STAINLESS STEEL CORNERS	OWNER	CONTRACTOR	CONTRACTOR		
STAINLESS STEEL PANELS AT DISH AREAS	OWNER	CONTRACTOR	CONTRACTOR		
STAINLESS STEEL PANELS AT HOOD AREAS	OWNER	CONTRACTOR	CONTRACTOR		
STEEL ANGLE FOR CHIPBOARD (GRATE COVER UNDER ICE MACHINE)	CONTRACTOR	CONTRACTOR	CONTRACTOR		
SOAP, CHEMICALS AND DISPENSERS	OWNER	CONTRACTOR	OWNER		
SODA SYSTEM	OWNER	CONTRACTOR	OWNER	OWNER	
SOUND SYSTEM	OWNER	CONTRACTOR	OWNER	OWNER	
TABLES	OWNER	CONTRACTOR	CONTRACTOR		
TELEVISIONS	OWNER	CONTRACTOR	CONTRACTOR	CONTRACTOR	
TILE AND GROUT FOR VESTIBULE, LOBBY, AND BAR	OWNER	CONTRACTOR	CONTRACTOR		
TILE AND GROUT(ONLY) FOR ALL AREAS EXCEPT VESTIBULE, LOBBY, AND BAR	CONTRACTOR	CONTRACTOR	CONTRACTOR		
TILE SEALERS AND ADHESIVES FOR ALL AREAS	CONTRACTOR	CONTRACTOR	CONTRACTOR		
TOILETS AND SEAT ACCESSORIES EXCEPT SOAP DISPENSERS	CONTRACTOR	CONTRACTOR	CONTRACTOR		
TOILET COMPARTMENTS	OWNER	CONTRACTOR	CONTRACTOR		
UPHOLSTERED BOOTH SEATS & BACKS	OWNER	CONTRACTOR	CONTRACTOR		
UPHOLSTERY OF SEATING BENCHES	OWNER	CONTRACTOR	CONTRACTOR		
VINYL WALL COVERING	OWNER	CONTRACTOR	CONTRACTOR		
WALK-IN COOLER/FREEZER	OWNER	CONTRACTOR	OWNER	CONTRACTOR	
WATER HEATER (NEW)	OWNER	CONTRACTOR	CONTRACTOR	CONTRACTOR	
WATER FILTERS	OWNER	CONTRACTOR	CONTRACTOR	CONTRACTOR	
WATER SOFTENER	OWNER	CONTRACTOR	OWNER	CONTRACTOR	
WINDOW BLINDS	CONTRACTOR	CONTRACTOR	CONTRACTOR		NOTES
WINDOW TYPES A, B & C	CONTRACTOR	CONTRACTOR	CONTRACTOR	CONTRACTOR	
WOOD TRUSSES & GLULAMS	CONTRACTOR	CONTRACTOR	CONTRACTOR		

NOTES:
1. CONTACT: PLANTS IN BOOK, CARDS, PARTY, PHONE # OWNER 904-[illegible]
2. CONTACT: CURTAIN AIRS, WOOD CARTOONS, PHONE # OWNER 352-[illegible]
3. CONTACT: [illegible] TRANS, PORT SIGNER, PHONE # [illegible] 386-[illegible] EXT. [illegible]
4. CONTACT: BLUE EMPIRE, ALBERT TA, PHONE # (770) 644-[illegible]
5. CONTACT: ABR MILLWORK, RANDY BRUMMER, PHONE # (770) 88-[illegible]
6. CONTACT: VENDOR ACCURATE, TOM FERNANDEZ HELLBURGE, PHONE # (770) 471-[illegible]

NOTE: THE RESPONSIBILITY BOILERPLATE REMOVED WORK ITEMS THAT ARE OWNER AND LICENSED CONTRACTOR REASONABLY OVERLOOK. CONTRACTOR SHALL CAREFULLY READ ITEMS ON THE DRAWINGS AND IN THE SPECIFICATIONS AND TAKE STEPS TO ENSURE THAT THESE ITEMS ARE PROVIDED AND INSTALLED AT THE LOCATIONS INDICATED ON THE DRAWINGS AT THE APPROPRIATE TIME IN THE CONSTRUCTION SCHEDULE.

PROJECT LOCATION



CATEGORY / SUBCATEGORY	MANUFACTURER	PRODUCT DESCRIPTION	APPROVAL NUMBER(S)
1. EXTERIOR DOORS			
SIDELIGHTS	KAWNEER	PREFAB VS-451	FL-7237
2. WINDOWS			
FIXED	KAWNEER	PREFAB VS-451	FL-7237
3. PANEL WALL			
EIFS	STO	STO POWERWALL STUCCO FINISH	FL-4713
4. ROOFING PRODUCTS			
SINGLE PLY ROOF SYSTEMS	DURO-LAST	MECHANICALLY AD MIL MEMBRANE	FL-944-R3

LONGHORN®

wd partners

7007 Discovery Blvd.
Dublin, OH 43017
614.634.7000 T
614.634.7777 F

wdpartners.com

atlanta boston chicago columbus dallas los angeles miami sacramento

ZONING:
KERRY NIELSON
GROWTH MANAGEMENT DEPARTMENT
409 FENNELL BOULEVARD
LADY LAKE, FLORIDA 32159
PHONE: 352-751-1520

BUILDING:
MARY PASAK
GROWTH MANAGEMENT DEPARTMENT
409 FENNELL BOULEVARD
LADY LAKE, FLORIDA 32159
PHONE: 352-751-1516

HEALTH
KIM PLEICONES
FLORIDA DEPARTMENT OF BUSINESS & PROFESSIONAL
400 WEST ROBINSON STREET
ORLANDO, 32801-1757
PHONE: 407-317-7842
FAX: 407-317-7832

FIRE
BRIAN BOWERS
PROGRESSIVE INSPECTIONS, INC.
10320 VON FRANKENSTEIN COURT
HOWEY IN THE HILLS, FLORIDA 34737
PHONE: 352-636-0024

SANITARY
KEN KEOUGH
TOWN OF LADY LAKE
PUBLIC WORKS DEPARTMENT
136 SKYLINE DRIVE
LADY LAKE, FLORIDA 32159
PHONE: 352-751-1526
FAX: 352-751-1595

TO ORDER PLANS GO TO ldiline.com

3461 MARICAMP ROAD
OCALA, FLORIDA 34471
PHONE: 352-286-9629

316 SW 33rd AVENUE
OCALA, FLORIDA 34474
PHONE: 352-401-3409

PUBLIC WORKS DEPARTMENT
136 SKYLINE DRIVE
LADY LAKE, FLORIDA 32159
PHONE: 352-751-1526
FAX: 352-751-1595

584 US HIGHWAY 441 N
LADY LAKE, FLORIDA 32159
PHONE: 352-430-2255

DRAWING TITLE ..... A1-01 — SHEET NUMBER / DRAWING I.D. NUMBER — FLOOR PLAN — SCALE: 1/4" = 1'-0" — A1-04 LIBRARY NUMBER / DRAWING SCALE

SECTION ..... — SECTION I.D. NUMBER / SHEET WHERE SECTION IS LOCATED

DETAIL ..... — DETAIL I.D. NUMBER / SHEET WHERE SECTION IS LOCATED

DETAIL (ENLARGED PLAN) ..... — AREA TO BE ENLARGED — DETAIL I.D. NUMBER / SHEET WHERE SECTION IS LOCATED

INTERIOR ELEVATION .... — ELEVATION I.D. NUMBER / SHEET WHERE SECTION IS LOCATED

CEILING HEIGHT ..... 9'-0" — CEILING HEIGHT ABOVE FINISHED FLOOR

RESTROOM ACCESSORIES .. 1 — RESTROOM ACCESSORY NUMBER

DOOR ..... 1 — DOOR NUMBER DESIGNATION

WINDOW ..... A — WINDOW NUMBER DESIGNATION

FINISH MATERIAL ..... P-1 TRIM ONLY — FINISH DESIGNATION / COMMENTS, IF APPLICABLE

KEYED NOTES ..... 1 — KEYED NOTE DESIGNATION ON APPLICABLE SHEET

REVISIONS ..... 2 — REVISION NUMBER / REVISED AREA CLOUDED

ELEVATION HEIGHT ..... 100'-0" TOP OF SLAB — ELEVATION HEIGHT / REFERENCE POINT

MILLWORK ITEM ..... 1 — MILLWORK NUMBER DESIGNATION

BUILDING CODE:	2004 FLORIDA BUILDING CODE
PLUMBING CODE:	2004 FLORIDA BUILDING CODE
MECHANICAL CODE:	2004 FLORIDA BUILDING CODE
ELECTRICAL CODE:	2005 NATIONAL ELECTRIC CODE
ACCESSIBILITY CODE:	

2. BUILDING DESCRIPTION:

CONSTRUCTION TYPE:	
USE GROUP:	A-2 ASSEMBLY
ALLOWABLE AREA:	
ALLOWABLE AREA INCREASE: (SEC. 506.3)	
TOTAL ALLOWABLE AREA:	57,000 SQFT.
ACTUAL AREA:	9,318 SQFT.
ALLOWABLE HEIGHT: (WITH SPRINKLER INCREASE)	2 STORY 60'
ACTUAL HEIGHT:	1 STORY 27'-7" MAX.

3. BUILDING AREA TABULATION:

VESTIBULE	87.0
HOSTESS/WAITING	344.4
DINING	3,348.0
REST ROOMS	349.0
KITCHEN	1,928.0
OFFICE	93.4
DRY GOODS	49.0
MECHANICAL/ELECTRICAL	70.0
TOTAL NET AREA	4,968.3
GROSS TOTAL AREA	9,318
FREEZER/COOLER	221.0
TRASH ENCLOSURE	43.0

4. OCCUPANCY/EGRESS:

DINING: 2,348 SQFT. / 15 SQFT. PER PERSON	156
KITCHEN: 1,928 SQFT. / 200 SQFT. PER PERSON	9
STORAGE: 1 TREAS. 93.0 SQFT. / 300 SQFT. PER PERSON	1
BATHS: 344.4 SQFT. / 5 SQFT. PER PERSON	70
TOTAL CALCULATED OCCUPANCY	236

ACTUAL GRIEVE OCCUPANCY:

MAXIMUM SEATING CAPACITY:	156
BATHS:	12
EMPLOYEES:	20
TOTAL:	228
EXITS REQUIRED: 1-2000	2
EXITS PROVIDED:	3

5. PLUMBING FIXTURES:

REQUIRED:	
MEN	2 WC, 2 UR, 2 LAV
WOMEN	2 WC, 2 LAV
SERVICE SINK:	1
DRINKING FOUNTAIN	1 (EXCEPTION)
PROVIDED:	
MEN	1 WC, 2 UR, 2 LAV
WOMEN	2 WC, 2 LAV
SERVICE SINK:	1
DRINKING FOUNTAIN	WATER SERVICE IS PROVIDED DIRECTLY TO THE CUSTOMER

A. ALL CONSTRUCTION SHALL COMPLY WITH APPLICABLE BUILDING CODES AND LOCAL RESTRICTIONS. CONTRACTORS MUST COMPLY WITH CONTRACTOR REGISTRATION REQUIREMENTS OF ALL GOVERNING AUTHORITIES.

B. APPROVED PLANS SHALL BE KEPT IN A PLAN BOX AND SHALL NOT BE USED BY SCROLL. ALL CONTRACTOR BIDS SHALL REFLECT MORE INFORMATION. CONTRACTOR SHALL MAINTAIN ONE COMPLETE SET OF PLANS ON THE PREMISES IN GOOD CONDITION AT ALL TIMES. THIS SHALL INCLUDE ALL ADDENDA.

C. THE CONTRACTOR SHALL FIELD VERIFY ALL CONDITIONS AND DIMENSIONS PRIOR TO STARTING ANY WORK, AND SHALL BE RESPONSIBLE FOR ALL WORK AND MATERIALS INCLUDING THOSE FURNISHED BY SUBCONTRACTORS AND OWNER.

D. DISCREPANCIES BETWEEN PORTIONS OF THE CONTRACT DOCUMENTS, DRAWINGS AND SPECIFICATIONS ARE NOT INTENDED. THE CONTRACTOR IS TO CLARIFY ANY SUCH DISCREPANCIES WITH THE OWNER PRIOR TO COMMENCING WORK.

E. STATED DIMENSIONS TAKE PRECEDENCE OVER GRAPHICS. DO NOT SCALE DRAWINGS TO DETERMINE LOCATIONS. THE OWNER SHALL BE NOTIFIED OF ANY SUCH DISCREPANCIES PRIOR TO CONTINUING WITH WORK.

F. CONTACT OWNER FOR INSTRUCTIONS PRIOR TO THE CONTINUATION OF WORK SHOULD ANY UNUSUAL CONDITIONS BECOME APPARENT DURING GRADING OR FOUNDATION CONSTRUCTION. EXISTING ELEVATIONS AND LOCATIONS TO BE JOINED SHALL BE VERIFIED BY THE CONTRACTOR PRIOR TO CONSTRUCTION. IF THEY DIFFER FROM THOSE SHOWN ON THE DRAWINGS, THE CONTRACTOR SHALL NOTIFY THE OWNER SO THAT MODIFICATIONS CAN BE MADE BEFORE PROCEEDING WITH THE WORK.

G. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO LOCATE ALL EXISTING UTILITIES SHOWN OR NOT AND TO PROTECT THEM FROM DAMAGE. THE CONTRACTOR SHALL BEAR THE EXPENSE OF REPAIR OR REPLACEMENT OF UTILITIES OR OTHER PROPERTY DAMAGED BY OPERATIONS IN CONJUNCTION WITH THE EXECUTION OF THE WORK, AFTER SO LOCATED.

H. COORDINATION TO REFER TO THESE DOCUMENTS AS WELL AS SPECIFICATIONS FOR IDENTIFICATION OF ALL OWNER SUPPLIED ITEMS. ALL ITEMS NOT MARKED AS OWNER SUPPLIED ARE TO BE SUPPLIED BY GENERAL CONTRACTOR, UNLESS NOTED OTHERWISE. ALL ITEMS ARE TO BE INSTALLED BY GENERAL CONTRACTOR.

I. FOR CONSTRUCTION DETAILS NOT SHOWN, USE THE MANUFACTURER'S PRODUCT SPECIFICATIONS, APPROVED SHOP DRAWINGS, INSTALLATION INSTRUCTIONS, AND DATA SHEETS IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.

K. FIRE EXTINGUISHERS TO BE INSTALLED AT HEIGHTS DESIGNATED BY OWNER AND IN COMPLIANCE WITH LOCAL FIRE CODE. FINAL FIRE EXTINGUISHER LOCATIONS SHALL BE APPROVED BY FIRE MARSHAL. GENERAL CONTRACTOR TO PROVIDE MINIMUM (3) ABC TEN POUND TYPE AND (1) CLASS K 10 POUNDS AT KITCHEN COOKLINE.

FIRE SPRINKLER AND FIRE ALARM PERMITS TO BE OBTAINED BY OTHERS

A FULL FIRE SPRINKLER SYSTEM IS REQUIRED TO BE PROVIDED & INSTALLED WITH ALL LOCAL CODE REQUIREMENTS & NFPA 13

7/26/07		
08/17/07	ISSUED FOR BID	

STORE NUMBER
—
WO PROJECT NUMBER
RHILH1263

T1

T1	TITLE SHEET	- 06/29/07
C3	COVER SHEET AND INDEX	- 06/29/07
	ALTA TITLE SURVEY	- 06/29/07
C1	SITE IMPROVEMENT PLAN	- 06/29/07
C1.1	SITE DETAILS	- 06/29/07
C2	SITE GRADING PLAN	- 06/29/07
C3	STORM WATER PLAN	- 06/29/07
C3.1	SEWER PROFILES	- 06/29/07
C4	EROSION CONTROL PLAN	- 06/29/07
C4.1	EROSION CONTROL DETAILS	- 06/29/07
C5	SITE UTILITY PLAN	- 06/29/07
C5.1	SITE UTILITY DETAILS	- 06/29/07
C6	SITE ILLUMINATION PLAN	- 06/29/07
L1	LANDSCAPE PLAN	- 06/29/07
L1.1	LANDSCAPE DETAILS	- 06/29/07
L1.2	PAD LANDSCAPE PLAN	- 06/29/07
L2	IRRIGATION PLAN	- 06/29/07
S1	FOUNDATION PLAN	- 06/29/07
S2	FOUNDATION DETAILS	- 06/29/07
S3	STRUCTURAL ROOF FRAMING PLAN	- 06/29/07
S4	FRAMING DETAILS	- 06/29/07
SS1	STRUCTURAL SPECIFICATIONS	- 06/29/07
A1	DIMENSIONED FLOOR PLAN	- 06/29/07
A2	NOTED PLAN	- 06/29/07
A3	SEATING & FLOOR FINISH PLAN	- 06/29/07
A4	REFLECTED CEILING PLAN	- 06/29/07
A5	ROOF PLAN	- 06/29/07
A6	DOOR SCHEDULE & ELEVATIONS	- 06/29/07
A7	WALL PLAN DETAILS AND FINISHES	- 06/29/07
A8	EXTERIOR ELEVATIONS	- 06/29/07
A9	EXTERIOR ELEVATIONS	- 06/29/07
A10	INTERIOR ELEVATIONS	- 06/29/07
A11	KITCHEN ELEVATIONS	- 06/29/07
A12	RESTROOM PLAN & ELEVATIONS	- 06/29/07
D1	BUILDING SECTIONS	- 06/29/07
D2	WALL SECTIONS & DETAILS	- 06/29/07
D3	WALL SECTIONS & DETAILS	- 06/29/07
D4	WALL SECTIONS & DETAILS	- 06/29/07
D5	DETAILS	- 06/29/07
D6	DETAILS	- 06/29/07
D7	DETAILS	- 06/29/07
D8	DETAILS	- 06/29/07
D9	DETAILS	- 06/29/07
D10	MILLWORK PLAN (BY ABR MILLWORK & LUMBER, INC.)	- 06/29/07
D11	MILLWORK DETAILS (BY ABR MILLWORK & LUMBER, INC.)	- 06/29/07
D12	MILLWORK DETAILS (BY ABR MILLWORK & LUMBER, INC.)	- 06/29/07
S1	ARCHITECTURAL SPECIFICATIONS	- 06/29/07
S2	ARCHITECTURAL SPECIFICATIONS	- 06/29/07
S3	ARCHITECTURAL SPECIFICATIONS	- 06/29/07
S4	ARCHITECTURAL SPECIFICATIONS	- 06/29/07
AS5	ARCHITECTURAL SPECIFICATIONS	- 06/29/07
AS6	ARCHITECTURAL SPECIFICATIONS	- 06/29/07
AS7	ARCHITECTURAL SPECIFICATIONS	- 06/29/07
AS8	ARCHITECTURAL SPECIFICATIONS	- 06/29/07
AS9	ARCHITECTURAL SPECIFICATIONS	- 06/29/07
AS10	ARCHITECTURAL SPECIFICATIONS	- 06/29/07
AS11	ARCHITECTURAL SPECIFICATIONS	- 06/29/07
AS12	ARCHITECTURAL SPECIFICATIONS	- 06/29/07
FS1	KITCHEN EQUIPMENT FLOOR PLAN	- 06/29/07
P1	UNDER FLOOR PLUMBING PLAN	- 06/29/07
P2	PLUMBING PLAN	- 06/29/07
P3	PLUMBING ROUGH-IN PLAN	- 06/29/07
P4	PLUMBING ROOF PLAN	- 06/29/07
P5	PLUMBING SCHEDULES & DETAILS	- 06/29/07
P6	PLUMBING DETAILS & RISERS	- 06/29/07
PS1	PLUMBING SPECIFICATIONS	- 06/29/07
PS2	PLUMBING SPECIFICATIONS	- 06/29/07
M1	MECHANICAL PLAN	- 06/29/07
M2	MECHANICAL SCHEDULES & DETAILS	- 06/29/07
M3	KITCHEN HOODS AND DETAILS	- 06/29/07
M4	KITCHEN HOODS AND DETAILS	- 06/29/07
MS1	MECHANICAL SPECIFICATIONS	- 06/29/07
E1	POWER PLAN	- 06/29/07
E2	LIGHTING PLAN	- 06/29/07
E3	COMMUNICATION PLAN	- 06/29/07
E4	ELECTRICAL ROUGH-IN PLAN	- 06/29/07
E5	ELECTRICAL ROOF PLAN	- 06/29/07
E6	PANEL SCHEDULES	- 06/29/07
E7	DETAILS & DIAGRAMS	- 06/29/07
E8	ALARM SYSTEMS (BY ADT)	- 06/29/07
E9	ALARM SYSTEMS (BY ADT)	- 06/29/07
E10	ALARM SYSTEMS (BY ADT)	- 06/29/07
ES1	ELECTRICAL SPECIFICATIONS	- 06/29/07
N1	FIELD NOTES	- 06/29/07
N2	FIELD NOTES	- 06/29/07