To Order Plans go to www.ldiline.com



NORTHLAKE #2 WEST ELEVATION WALL DEMO NOTES:

SCOPE OF WORK:
EXISTING METAL PANELS & 8'-0" CMU WALL BEHIND BRICK VENEER ARE TO REMAIN. HOLES WILL BE CUT IN METAL PANELS CMU WALL FOR NEW OPENINGS.

FROM OUTSIDE: (PROTECT EXISTING GAS PIPE, STORM DRAIN, & IRRIGATION PIPES)
- REMOVE & PROPERLY DISPOSE OF GUTTERS & DOWNSPOUTS.
- REMOVE & STORE WALL PACK LIGHT NEAR COL. LINE 1-1. REMOVE ASSOCIATED ELECTRICAL COMPONENTS, CONDUIT, WIRING, & DISPOSE
- REMOVE CONDENSER UNITS & STORE.
- REMOVE & DISPOSE OF ELECTRICAL DISCONNECTS, CONDUIT, WIRING, & CONDENSE PIPE ASSOCIATED w/ CONDENSER UNITS.
- REMOVE & DISPOSE OF ELECTRICAL METERS & MAIN FEEDERS & CONDUIT ENTERING BUILDING AT FLOOR LEVEL BETWEEN COL. LINES 4-1 &5-1
- REMOVE GAS METER AND STORE FOR POSSIBLE REUSE AT THIS LOCATION. TEMPORARILY CAP SERVICE. CAP UNDERGROUND GAS SERVICE. REMOVE SERVICE PIPE PASSING THRU WALL AND TEMP. CAP SERVICE INSIDE BUILDING. OWNER MAY WISH TO LEAVE PIPING INSIDE BUILDING.
- REMOVE & PROPERLY DISPOSE OF EXTERIOR UTILITY BRICK, LINTELS, BRICK TIES, EXTERIOR SHEATHING, METAL WALL PANELS REMAIN. AT BOTTOM 8'-0" OF WALL CHIP AWAY GROUT FILLING AIRSPACE BEHIND BRICK TO EXPOSE 8" CMU. IF THERE IS NO GROUT REUSE BRICK TIES ATTACHED TO SURFACE OF WHAT IS 8" CMU.
- AT TALL ENTRYWAY RECESS: REMOVE & DISPOSE OF EXTERIOR UTILITY BRICK, LINTEL ABOVE OPENING, SOFFIT STRUCTURE & GLASS STOREFRONT. REMOVE AND DISPOSE OF EXTERIOR SHEATHING & METAL STUDS ONCE BACKING UP THE EXISTING BRICK.

FROM INSIDE:
- REMOVE AND DISPOSE OF SHELVING.

PARKING LOT SOUTH ELEVATION WALL DEMO NOTES:

SCOPE OF WORK:
REMOVE ALL MECHANICAL, & ELECTRICAL DEVICES LEAVING ONLY EXISTING PRE-ENG. BUILDING COLUMNS, GIRTS, AND STEEL FRAMING.

FROM OUTSIDE:
- REMOVE & PROPERLY DISPOSE OF RAKE FLASHING.
- REMOVE & STORE WALL PACK LIGHTS NEAR COLUMNS LINES K,G,&E. REMOVE ASSOCIATED ELECTRICAL COMPONENTS, CONDUIT, WIRING, & DISPOSE.
- REMOVE & DISPOSE OF DUCT NEAR COL. LINE C
- REMOVE & DISPOSE OF VENT NEAR COL. LINE E
- REMOVE & DISPOSE OF ANY OTHER ITEMS PASSING THROUGH EXISTING METAL PANELS

FROM INSIDE:
- REMOVE INTERIOR METAL LINER PANELS IF REQUIRED FOR CONSTRUCTION.

DRIVEWAY SIDE EAST ELEVATION WALL DEMO NOTES:

SCOPE OF WORK:
EXISTING METAL PANELS ARE TO REMAIN ON THIS WALL w/ HOLES CUT FOR OPENINGS. INTERIOR INSULATION TO REMAIN.

FROM OUTSIDE:
FOR DEMOLITION OF WALL BETWEEN COL. LINES 6&7: REFER TO DEMO NOTES FOR NORTH WALL.
FOR DEMOLITION OF WALL BETWEEN COL. LINES 1&6:
- REMOVE & PROPERLY DISPOSE OF GUTTER & DOWNSPOUTS.
- REMOVE AND PROPERLY DISPOSE OF PROTRUDING DUCT & CONDUIT NEAR COL. LINE 1. REATTACH & PREPARE BENT, DENTED METAL WALL PANELS
- CLEAN METAL PANELS TO PREPARE FOR NEW SHEATHING ATTACHMENT.
- REMOVE & STORE WALL PACK LIGHT. REMOVE ASSOCIATED ELECTRICAL COMPONENTS, CONDUIT, & WIRING & DISPOSE.
- CUT EXISTING METAL PANEL & GIRTS TO CREATE OPENING FOR NEW STOREFRONT & GARAGE DOORS. REFER TO ARCHITECTURAL & STRUCTURAL DWGS FOR NEW WORK AT THESE LOCATIONS. PROPERLY DISPOSE OF MATERIALS.
- PLEASE NOTE THAT THERE IS A ROUGH CONCRETE SLAB EDGE OF THIS SIDE OF THE BUILDING. IT IS ANTICIPATED THAT NEW SIDE WALLS & LANDSCAPING WILL CONCEAL THE ROUGH CONCRETE.

METROMONT PARKWAY NORTH ELEVATION WALL DEMO NOTES:

SCOPE OF WORK:
REMOVAL OF ENTIRE WALL STRUCTURE LEAVING ONLY PRE-ENG. BUILDING COLS., FRAMING, & FLOOR STRUCTURE.

FROM OUTSIDE:
- REMOVE & PROPERLY DISPOSE OF EXTERIOR UTILITY BRICK, BRICK TIES, LINTELS, EXTERIOR SHEATHING, METAL DECKING @ WINDOW SILL & METAL STUDS.
- REMOVE COPING AT TOP OF PARAPET & LINER PANEL ON BACK OF PARAPET AND PROPERLY DISPOSE

FROM INSIDE:
- REMOVE & PROPERLY DISPOSE OF EXISTING GWB & PLYWOOD (COL. LINES A-F) INSULATION & STUD FRAMING. REMOVE & DISPOSE OF PLUMBING PIPES & ELECTRICAL CONDUIT & COMPONENTS & ELECTRICAL CONDUIT 1'-0" ABOVE FLOOR.
- EXISTING ACT GRID CEILINGS SHALL ONLY BE REMOVED TO NEXT MAIN RUNNER CLOSEST TO EXTERIOR WALL. ANY LIGHTS & DIFFUSERS REMOVED SHALL BE LEFT STORED IN SAME ROOM.
- MAINTAIN EXISTING STRUCTURAL INTEGRITY OF FRAMING AND FLOOR SYSTEMS.
- REMOVE AND PROPERLY DISPOSE OF EXISTING STOREFRONT WINDOWS.

DEMOLITION SCOPING STATEMENT

- CARDINAL DIRECTIONS ON THIS SHEET ARE WITH RESPECT TO TRUE NORTH.

- DEMOLITION IS LIMITED TO EXTERIOR WALLS, AS DESCRIBED IN OTHER NOTES ON THIS SHEET.

- IN THE AREAS BOUNDED BY COL. LINES 5-1 & 7-1 AND BY F-1 & L WALLS, PLUMBING FIXTURES, CEILING, LIGHTS ETC. ARE TO REMAIN UNTOUCHED EXCEPT WHERE "[illegible]" SYMBOLS SPECIFICALLY DENOTE A DEMO ITEM. THE INTENT IS THAT THESE AREAS WILL BE UPGRADED BY FUTURE TENANTS.

DEMOLITION NOTES:

1. REMOVE AND PROPERLY DISPOSE OF EXIST. SECTIONAL GARAGE DOORS. REMOVE EXTERIOR FLASHING & INTERIOR TRACK SUPPORTS & OPENING MECHANISM.
2. REMOVE AND PROPERLY DISPOSE OF EXISTING DOOR, FRAME, AND HARDWARE IN ITS ENTIRETY.
3. REMOVE AND PROPERLY DISPOSE OF EXIST. SECTIONAL GARAGE DOORS. REMOVE EXTERIOR FLASHING & INTERIOR TRACK SUPPORTS & OPENING MECHANISM. STRUCTURAL JAMB CHANNELS & HEADERS SHALL REMAIN IN PLACE.
4. REMOVE 4'-0"x7'-0" HIGH SECTION OF DRYWALL & STUDS.
5. REMOVE ACT CEILING TILES AND TRACK TO NEAREST MAIN RUNNER TO MAKE WAY FOR NEW WALL.
6. REMOVE AND PROPERLY DISPOSE OF ROOF & CMU WALLS. PATCH FLOOR TO A SMOOTH LEVEL SURFACE.
7. REMOVE AND PROPERLY DISPOSE OF PORTION OF EXISTING STUD WALL.
8. REMOVE AND PROPERLY DISPOSE OF EXIST. FLOOR FINISH, CLEAN & PREP CONC. FOR NEW FLOOR FINISH MATERIAL PER THE FINISH SCHEDULE.
9. EXISTING GAS WATER HEATER. GC SHALL VERIFY IF WATER HEATER IS IN USE & WHAT AREA IT SERVICES. IF WATER HEATER IS NOT IN USE REMOVE & DISPOSE OF IT ALONG w/ EXHAUST VENT DUCT. CAP WATER LINES & GAS SERVICE PIPE.IF WATER HEATER IS IN USE CONTACT ARCHITECT TO DETERMINE WHEN TO REMOVE WATER HEATER.
10. TAKE CARE TO REMOVE ONLY WHAT IS REQUIRED & PREPARE EXISTING MATERIALS FOR NEW DESIGN. SEE WEST WALL DEMO. NOTES ON THIS PAGE.
11. REMOVE & DISPOSE OF ROOF VENT OR EXHAUST STRUCTURES. PREPARE ROOF OPENING FOR REPAIR.
12. REMOVE & DISPOSE OF UNIT HEATER EXHAUST STRUCTURE. PREPARE ROOF OPENING FOR REPAIR.
13. REMOVE AND PROPERLY DISPOSE OF EXISTING UP AIR LOUVERS AND FANS. LEAVE STRUCTURAL ANGLE FRAMING IN LOCATIONS NOT REPLACED BY NEW OPENING. REMOVE ASSOCIATED ELECTRICAL COMPONENTS, CONDUIT, WIRING, & DISPOSE.
14. G.C. TO VERIFY USE OF VTR. THESE CAN BE SEEN IN THE ROOF OF THE SECOND FLOOR. NOTIFY ARCHITECT OF USE. IF VTR'S ARE FOUND TO BE OF NO USE G.C. SHALL REMOVE & DISPOSE OF PIPE CAPPING AT 1ST FLOOR SLAB. PREPARE ROOF OPENING FOR REPAIR.
15. REMOVE AND PROPERLY DISPOSE OF EXISTING INTERIOR GWB & METAL STUD WALL.
16. REMOVE EXISTING DOCK LEVELER & DISPOSE. EDGE ANGLE TO REMAIN. CLEAN & REMOVE SAND AND DEBRIS FROM PI. PREPARE PIT FOR NEW CONC. SLAB INFILL. REFER TO STRUCTURAL DWGS.
17. AT NEW STOREFRONT WINDOWS EXISTING WALLS SHALL BE CUT BACK 1'-0" FROM INSIDE OF EXISTING WINDOW FRAME.

GENERAL DEMO. NOTES:

1. G.C. TO BRING ANY DISCREPANCIES FROM THE PLAN TO THE ATTENTION OF THE ARCHITECT. IF THERE IS A QUESTION ABOUT DEMOLITION DO NOT HESITATE TO CALL ARCHITECT.
2. PATCH & REPAIR SLAB WHERE DAMAGE OCCURS DUE TO DEMOLITION.
3. BUILDING PLUMBING, MECHANICAL, & ELECTRICAL WILL BE REMOVED AS NOTED ON THIS PLAN. CAP PLUMBING, ELECTRICAL CONDUIT IN THE SLAB EXPOSED DUE TO DEMO. TO 1'-0" ABOVE FLOOR.
4. IT IS THE RESPONSIBILITY OF THE G.C. TO MAINTAIN A CLEAN AND SAFE ENVIRONMENT DURING DEMOLITION.
5. TAKE MEASURE NECESSARY TO PROTECT EXPOSED INTERIOR SPACES FROM WEATHER & TRESPASSING ONCE EXTERIOR WALLS ARE REMOVED.
6. ALL BRACING IN ROOF OR WALLS TO REMAIN.

KEY:

[solid line]	EXISTING WALL TO REMAIN
[dashed line]	EXISTING WALL TO BE REMOVED
[door swing]	EXISTING DOOR TO BE REMOVED

1 DEMOLITION PLAN - MAIN LEVEL
SCALE: 1/8" = 1'-0"
N TRUE

REVISIONS:

WARNING
IT IS A VIOLATION OF THE LAW FOR ANY PERSON, UNLESS ACTING UNDER THE DIRECTION OF THE ARCHITECT, TO ALTER OR REPRODUCE THESE DRAWINGS IN ANY WAY.

CERT. NO. 51827
8971
6/12/07

MWT

Charlotte, North Carolina
MWT Architecture, P.C.
520 Collins Aikman Drive - Suite 200
Charlotte, NC 28262
Ph. 704.947.9712 Fax: 595.1725

Northlake Pavilion Building #3
Metromont Pkwy & Statesville Rd
Charlotte, NC

PROJECT NO.	05271-3
DATE:	07/10/07
DRAWN BY:	JRE
CHKD BY:	JDW

FIRST FLOOR DEMO PLAN

SHEET AD101

THIS DOCUMENT IS THE PRODUCT AND EXCLUSIVE PROPERTY OF MWT ARCHITECTURE. NEITHER THE DOCUMENT NOR INFORMATION IT CONTAINS MAY BE COPIED, DISCLOSED TO OTHERS OR USED IN CONNECTION WITH ANY WORK OR PROJECT OTHER THAN THE SPECIFIC PROJECT FOR WHICH THEY HAVE BEEN PREPARED AND DEVELOPED WITHOUT THE WRITTEN CONSENT OF MWT ARCHITECTURE. © COPYRIGHT 2006 MWT ARCHITECTURE

To Order Plans go to www.ldiline.com

REVISIONS:



DEMOLITION NOTES:

1. REMOVE AND PROPERLY DISPOSE OF EXIST. SECTIONAL GARAGE DOORS. REMOVE EXTERIOR FLASHING & INTERIOR TRACK SUPPORTS & OPENING MECHANISM.
2. REMOVE AND PROPERLY DISPOSE OF EXISTING DOOR, FRAME, AND HARDWARE IN ITS ENTIRETY.
3. REMOVE AND PROPERLY DISPOSE OF EXIST. SECTIONAL GARAGE DOORS. REMOVE EXTERIOR FLASHING & INTERIOR TRACK SUPPORTS & OPENING MECHANISM. STRUCTURAL JAMB CHANNELS & HEADERS SHALL REMAIN IN PLACE.
4. REMOVE 4'-0"x7'-0" HIGH SECTION OF DRYWALL & STUDS.
5. REMOVE ACT CEILING TILES AND TRACK TO NEAREST MAIN RUNNER TO MAKE WAY FOR NEW WALL.
6. REMOVE AND PROPERLY DISPOSE OF ROOF & CMU WALLS. PATCH FLOOR TO A SMOOTH LEVEL SURFACE.
7. REMOVE AND PROPERLY DISPOSE OF PORTION OF EXISTING STUD WALL.
8. REMOVE AND PROPERLY DISPOSE OF EXIST. FLOOR FINISH, CLEAN & PREP CONC. FOR NEW FLOOR FINISH MATERIAL PER THE FINISH SCHEDULE.
9. EXISTING GAS WATER HEATER. GC SHALL VERIFY IF WATER HEATER IS IN USE & WHAT AREA IT SERVICES. IF WATER HEATER IS NOT IN USE REMOVE & DISPOSE OF IT ALONG w/ EXHAUST VENT DUCT. CAP WATER LINES & GAS SERVICE PIPE.IF WATER HEATER IS IN USE CONTACT ARCHITECT TO DETERMINE WHEN TO REMOVE WATER HEATER.
10. TAKE CARE TO REMOVE ONLY WHAT IS REQUIRED & PREPARE EXISTING MATERIALS FOR NEW DESIGN. SEE WEST WALL DEMO. NOTES ON THIS PAGE.
11. REMOVE & DISPOSE OF ROOF VENT OR EXHAUST STRUCTURES. PREPARE ROOF OPENING FOR REPAIR.
12. REMOVE & DISPOSE OF UNIT HEATER EXHAUST STRUCTURE. PREPARE ROOF OPENING FOR REPAIR.
13. REMOVE AND PROPERLY DISPOSE OF EXISTING UP AIR LOUVERS AND FANS. LEAVE STRUCTURAL ANGLE FRAMING IN LOCATIONS NOT REPLACED BY NEW OPENING. REMOVE ASSOCIATED ELECTRICAL COMPONENTS, CONDUIT, WIRING, & DISPOSE.
14. G.C. TO VERIFY USE OF VTR. THESE CAN BE SEEN IN THE ROOF OF THE SECOND FLOOR. NOTIFY ARCHITECT OF USE. IF VTR'S ARE FOUND TO BE OF NO USE G.C. SHALL REMOVE & DISPOSE OF PIPE CAPPING AT 1ST FLOOR SLAB. PREPARE ROOF OPENING FOR REPAIR.
15. REMOVE AND PROPERLY DISPOSE OF EXISTING INTERIOR GWB & METAL STUD WALL.
16. REMOVE EXISTING DOCK LEVELER & DISPOSE. EDGE ANGLE TO REMAIN. CLEAN & REMOVE SAND AND DEBRIS FROM PL. PREPARE PIT FOR NEW CONC. SLAB INFILL. REFER TO STRUCTURAL DWGS.
17. AT NEW STOREFRONT WINDOWS EXISTING WALLS SHALL BE CUT BACK 1'-0" FROM INSIDE OF EXISTING WINDOW FRAME.

GENERAL DEMO. NOTES:

1. G.C. TO BRING ANY DISCREPANCIES FROM THE PLAN TO THE ATTENTION OF THE ARCHITECT. IF THERE IS A QUESTION ABOUT DEMOLITION DO NOT HESITATE TO CALL ARCHITECT.
2. PATCH & REPAIR SLAB WHERE DAMAGE OCCURS DUE TO DEMOLITION.
3. BUILDING PLUMBING, MECHANICAL, & ELECTRICAL WILL BE REMOVED AS NOTED ON THIS PLAN. CAP PLUMBING, ELECTRICAL CONDUIT IN THE SLAB EXPOSED DUE TO DEMO. TO 1'-0" ABOVE FLOOR.
4. IT IS THE RESPONSIBILITY OF THE G.C. TO MAINTAIN A CLEAN AND SAFE ENVIRONMENT DURING DEMOLITION.
5. TAKE MEASURE NECESSARY TO PROTECT EXPOSED INTERIOR SPACES FROM WEATHER & TRESPASSING ONCE EXTERIOR WALLS ARE REMOVED.
6. ALL BRACING IN ROOF OR WALLS TO REMAIN.

KEY:

——	EXISTING WALL TO REMAIN
- - - -	EXISTING WALL TO BE REMOVED
(door symbol)	EXISTING DOOR TO BE REMOVED

NORTHLAKE #2 WEST ELEVATION WALL DEMO NOTES:

[illegible]

PARKING LOT SOUTH ELEVATION WALL DEMO NOTES:

[illegible]

DRIVEWAY SIDE EAST ELEVATION WALL DEMO NOTES:

[illegible]

METROMONT PARKWAY NORTH ELEVATION WALL DEMO NOTES:

[illegible]

DEMOLITION SCOPING STATEMENT

- CARDINAL DIRECTIONS ON THIS SHEET ARE WITH RESPECT TO TRUE NORTH.
- DEMOLITION IS LIMITED TO EXTERIOR WALLS, AS DESCRIBED IN OTHER NOTES ON THIS SHEET.

IN THE AREAS BOUNDED BY COL. LINES 6-1 & 7-1 AND BY F-1 & [illegible] WALLS, PLUMBING FIXTURES, CEILING, LIGHTS ETC. ARE TO REMAIN UNTOUCHED EXCEPT WHERE "[1]" SYMBOLS SPECIFICALLY DENOTE A DEMO ITEM. THE INTENT IS THAT THESE AREAS WILL BE UPGRADED BY FUTURE TENANTS.

1 DEMOLITION PLAN - SECOND FLOOR
SCALE: 1/8" = 1'-0"

N TRUE

WARNING: IT IS A VIOLATION OF THE LAW FOR ANY PERSON, UNLESS ACTING UNDER THE DIRECTION OF THE ARCHITECT, TO ALTER OR REPRODUCE THESE DRAWINGS IN ANY WAY.

MWT

Charlotte, North Carolina
MWT Architecture, P.C.
520 Collins Aikman Drive - Suite 200
Charlotte, NC 28262
Ph. 704.547.9772 Fax: 593.1725

Northlake Pavilion Building #3
Metromont Pkwy & Statesville Rd
Charlotte, NC

PROJECT NO.:	05271-3
DATE:	07/10/07
DRAWN BY:	JRF
CHKD. BY:	JDW

SECOND FLOOR DEMO PLAN

SHEET AD102

To Order Plans go to www.ldiline.com



DEMOLITION NOTES:

1. REMOVE AND PROPERLY DISPOSE OF EXIST. SECTIONAL GARAGE DOORS. REMOVE EXTERIOR FLASHING & INTERIOR TRACK SUPPORTS & OPENING MECHANISM.
2. REMOVE AND PROPERLY DISPOSE OF EXISTING DOOR, FRAME, AND HARDWARE IN ITS ENTIRETY.
3. REMOVE AND PROPERLY DISPOSE OF EXIST. SECTIONAL GARAGE DOORS. REMOVE EXTERIOR FLASHING & INTERIOR TRACK SUPPORTS & OPENING MECHANISM. STRUCTURAL JAMB CHANNELS & HEADERS SHALL REMAIN IN PLACE.
4. REMOVE 4'-0"x7'-0" HIGH SECTION OF DRYWALL & STUDS.
5. REMOVE ACT CEILING TILES AND TRACK TO NEAREST MAIN RUNNER TO MAKE WAY FOR NEW WALL.
6. REMOVE AND PROPERLY DISPOSE OF ROOF & CMU WALLS. PATCH FLOOR TO A SMOOTH LEVEL SURFACE.
7. REMOVE AND PROPERLY DISPOSE OF PORTION OF EXISTING STUD WALL.
8. REMOVE AND PROPERLY DISPOSE OF EXIST. FLOOR FINISH, CLEAN & PREP CONC. FOR NEW FLOOR FINISH MATERIAL PER THE FINISH SCHEDULE.
9. EXISTING GAS WATER HEATER. GC SHALL VERIFY IF WATER HEATER IS IN USE & WHAT AREA IT SERVICES. IF WATER HEATER IS NOT IN USE REMOVE & DISPOSE OF IT ALONG w/ EXHAUST VENT DUCT. CAP WATER LINES & GAS SERVICE PIPE.IF WATER HEATER IS IN USE CONTACT ARCHITECT TO DETERMINE WHEN TO REMOVE WATER HEATER.
10. TAKE CARE TO REMOVE ONLY WHAT IS REQUIRED & PREPARE EXISTING MATERIALS FOR NEW DESIGN. SEE WEST WALL DEMO. NOTES ON THIS PAGE.
11. REMOVE & DISPOSE OF ROOF VENT OR EXHAUST STRUCTURES. PREPARE ROOF OPENING FOR REPAIR.
12. REMOVE & DISPOSE OF UNIT HEATER EXHAUST STRUCTURE. PREPARE ROOF OPENING FOR REPAIR.
13. REMOVE AND PROPERLY DISPOSE OF EXISTING UP AIR LOUVERS AND FANS. LEAVE STRUCTURAL ANGLE FRAMING IN LOCATIONS NOT REPLACED BY NEW OPENING. REMOVE ASSOCIATED ELECTRICAL COMPONENTS, CONDUIT, WIRING, & DISPOSE.
14. G.C. TO VERIFY USE OF VTR. THESE CAN BE SEEN IN THE ROOF OF THE SECOND FLOOR. NOTIFY ARCHITECT OF USE. IF VTR'S ARE FOUND TO BE OF NO USE G.C. SHALL REMOVE & DISPOSE OF PIPE CAPPING AT 1ST FLOOR SLAB. PREPARE ROOF OPENING FOR REPAIR.
15. REMOVE AND PROPERLY DISPOSE OF EXISTING INTERIOR GWB & METAL STUD WALL.
16. REMOVE EXISTING DOCK LEVELER & DISPOSE. EDGE ANGLE TO REMAIN. CLEAN & REMOVE SAND AND DEBRIS FROM PI. PREPARE PIT FOR NEW CONC. SLAB INFILL. REFER TO STRUCTURAL DWGS.
17. AT NEW STOREFRONT WINDOWS EXISTING WALLS SHALL BE CUT BACK 1'-0" FROM INSIDE OF EXISTING WINDOW FRAME.

GENERAL DEMO. NOTES:

1. G.C. TO BRING ANY DISCREPANCIES FROM THE PLAN TO THE ATTENTION OF THE ARCHITECT. IF THERE IS A QUESTION ABOUT DEMOLITION DO NOT HESITATE TO CALL ARCHITECT.
2. PATCH & REPAIR SLAB WHERE DAMAGE OCCURS DUE TO DEMOLITION.
3. BUILDING PLUMBING, MECHANICAL, & ELECTRICAL WILL BE REMOVED AS NOTED ON THIS PLAN. CAP PLUMBING, ELECTRICAL CONDUIT IN THE SLAB EXPOSED DUE TO DEMO. TO 1'-0" ABOVE FLOOR.
4. IT IS THE RESPONSIBILITY OF THE G.C. TO MAINTAIN A CLEAN AND SAFE ENVIRONMENT DURING DEMOLITION.
5. TAKE MEASURE NECESSARY TO PROTECT EXPOSED INTERIOR SPACES FROM WEATHER & TRESPASSING ONCE EXTERIOR WALLS ARE REMOVED.
6. ALL BRACING IN ROOF OR WALLS TO REMAIN.

KEY:

- EXISTING WALL TO REMAIN
- EXISTING WALL TO BE REMOVED
- EXISTING DOOR TO BE REMOVED

NORTHLAKE #2 WEST ELEVATION WALL DEMO NOTES:

SCOPE OF WORK:
EXISTING METAL PANELS & 8"-0" CMU WALL BEHIND BRICK VENEER ARE TO REMAIN. HOLES WILL BE CUT IN METAL PANELS CMU WALL FOR NEW OPENINGS.

FROM OUTSIDE: (PROTECT EXISTING GAS PIPE, STORM DRAIN, & IRRIGATION PIPES)
- REMOVE & PROPERLY DISPOSE OF GUTTERS & DOWNSPOUTS.
- REMOVE & STORE WALL PACK LIGHT NEAR COL. LINE 5-1. REMOVE ASSOCIATED ELECTRICAL COMPONENTS, CONDUIT, WIRING, & DISPOSE.
- REMOVE CONDENSER UNITS & STORE.
- REMOVE & DISPOSE OF ELECTRICAL DISCONNECTS, CONDUIT, WIRING, & CONDENSATE PIPE ASSOCIATED w/ CONDENSER UNITS.
- REMOVE & DISPOSE OF ELECTRICAL METERS & MAIN FEEDERS & CONDUIT ENTERING BUILDING AT FLOOR LEVEL BETWEEN COL. LINES 4-1 & 5-1
- REMOVE GAS METER AND STORE FOR POSSIBLE REUSE AT THIS LOCATION. TEMPORARILY CAP SERVICE OR UNDERGROUND GAS SERVICE. REMOVE SERVICE PIPE PASSING THRU WALL AND TEMP. CAP SERVICE INSIDE BUILDING. OWNER MAY WISH TO LEAVE PIPING INSIDE BUILDING.
- REMOVE & PROPERLY DISPOSE OF EXTERIOR UTILITY BRICK, LINTELS, BRICK TIES, EXTERIOR SHEATHING, METAL WALL PANELS REMAIN AT BOTTOM 8'-0" OF WALL CHIP AWAY GROUT FILLING AIRSPACE BEHIND BRICK TO EXPOSE 8" CMU. IF THERE IS NO GROUT REUSE BRICK TIES ATTACHED TO SURFACE OF WHAT IS 8" CMU.
-AT TALL ENTRYWAY RECESS: REMOVE & DISPOSE OF EXTERIOR UTILITY BRICK, LINTEL ABOVE OPENING, SOFFIT STRUCTURE & GLASS STOREFRONT. REMOVE AND DISPOSE OF EXTERIOR SHEATHING & METAL STUDS ONCE BACKING UP THE EXISTING BRICK.

FROM INSIDE:
- REMOVE AND DISPOSE OF SHELVING.

PARKING LOT SOUTH ELEVATION WALL DEMO NOTES:

SCOPE OF WORK:
REMOVE ALL MECHANICAL & ELECTRICAL DEVICES LEAVING ONLY EXISTING PRE-ENG BUILDING COLUMNS, GIRTS, AND STEEL FRAMING.

FROM OUTSIDE:
- REMOVE & PROPERLY DISPOSE OF RAKE FLASHING.
- REMOVE & STORE WALL PACK LIGHTS NEAR COLUMNS LINES K, G, & E. REMOVE ASSOCIATED ELECTRICAL COMPONENTS, CONDUIT, WIRING, & DISPOSE.
- REMOVE & DISPOSE OF DUCT NEAR COL. LINE G
- REMOVE & DISPOSE OF VENT NEAR COL. LINE E
- REMOVE & DISPOSE OF ANY OTHER ITEMS PASSING THROUGH EXISTING METAL PANELS.

FROM INSIDE:
- REMOVE INTERIOR METAL LINER PANELS IF REQUIRED FOR CONSTRUCTION.

DRIVEWAY SIDE EAST ELEVATION WALL DEMO NOTES:

SCOPE OF WORK:
EXISTING METAL PANELS ARE TO REMAIN ON THIS WALL w/ HOLES CUT FOR OPENINGS. INTERIOR INSULATION TO REMAIN.

FROM OUTSIDE:
FOR DEMOLITION OF WALL BETWEEN COL. LINES 6&7: REFER TO DEMO NOTES FOR NORTH WALL
FOR DEMOLITION OF WALL BETWEEN COL. LINES 1&6:
- REMOVE & PROPERLY DISPOSE OF GUTTER & DOWNSPOUTS.
- REMOVE AND PROPERLY DISPOSE OF PROTRUDING DUCT & CONDUIT NEAR COL. LINE 1. REATTACH & PREPARE BENT, DENTED METAL WALL PANELS.
- CLEAN METAL PANELS TO PREPARE FOR NEW SHEATHING ATTACHMENT.
- REMOVE & STORE WALL PACK LIGHT. REMOVE ASSOCIATED ELECTRICAL COMPONENTS, CONDUIT, & WIRING & DISPOSE.
- CUT EXISTING METAL PANEL & GIRTS TO CREATE OPENING FOR NEW STOREFRONT & GARAGE DOORS. REFER TO ARCHITECTURAL & STRUCTURAL DWGS FOR NEW WORK AT THESE LOCATIONS. PROPERLY DISPOSE OF MATERIALS.
- PLEASE NOTE THAT THERE IS A ROUGH CONCRETE SLAB EDGE OF THIS SIDE OF THE BUILDING. IT IS ANTICIPATED THAT NEW SIDE WALLS & LANDSCAPING WILL CONCEAL THE ROUGH CONCRETE.

METROMONT PARKWAY NORTH ELEVATION WALL DEMO NOTES:

SCOPE OF WORK:
REMOVAL OF ENTIRE WALL STRUCTURE LEAVING ONLY PRE-ENG. BUILDING COLS., FRAMING, & FLOOR STRUCTURE.

FROM OUTSIDE:
- REMOVE & PROPERLY DISPOSE OF EXTERIOR UTILITY BRICK, BRICK TIES, LINTELS, EXTERIOR SHEATHING, METAL DECKING @ WINDOW SILL & METAL STUDS.
- REMOVE COPING AT TOP OF PARAPET & LINER PANEL ON BACK OF PARAPET AND PROPERLY DISPOSE.

FROM INSIDE:
- REMOVE & PROPERLY DISPOSE OF EXISTING GWB & PLYWOOD (COL. LINES A-F) INSULATION & STUD FRAMING. REMOVE & DISPOSE OF PLUMBING PIPES & ELECTRICAL CONDUIT & COMPONENTS & ELECTRICAL CONDUIT 1'-0" ABOVE FLOOR.
- EXISTING ACT GRID CEILINGS SHALL ONLY BE REMOVED TO NEXT MAIN RUNNER CLOSEST TO EXTERIOR WALL. ANY LIGHTS & DIFFUSERS REMOVED SHALL BE LEFT STORED IN SAME ROOM.
- MAINTAIN EXISTING STRUCTURAL INTEGRITY OF FRAMING AND FLOOR SYSTEMS.
- REMOVE AND PROPERLY DISPOSE OF EXISTING STOREFRONT WINDOWS.

DEMOLITION SCOPING STATEMENT

- CARDINAL DIRECTIONS ON THIS SHEET ARE WITH RESPECT TO TRUE NORTH.
- ANTICIPATED DEMOLITION ON THE ROOF IS LIMITED TO STRUCTURES SHOWN. G.C. SHALL NOTIFY ARCHITECT OF ROOF STRUCTURES NOT INDICATED ON THIS DRAWING.
- G.C. SHALL INSPECT ROOF FLASHING, PANELS, RIDGE CAP, ETC. AND NOTIFY ARCHITECT OF ANY NEEDED REPAIRS AND SIGNS OF DETERIORATION.
-REFER TO A101 FOR DEMO OF EXTERIOR WALLS, GUTTERS & COPPING.
- PATCH & REPAIR ROOF WHERE ANY DAMAGE OCCURS DUE TO DEMOLITION.

1 DEMOLITION PLAN - ROOF

SCALE: 1/8" = 1'-0"

REVISIONS:

MWT

Charlotte, North Carolina
MWT Architecture, P.C.

Northlake Pavilion Building #3
Metromont Pkwy & Statesville Rd
Charlotte, NC

PROJECT NO.	05771-3
DATE:	07/10/07
DRAWN BY:	JRL
CHKD. BY:	JDW

DEMOLITION ROOF PLAN

SHEET AD200

THIS DOCUMENT IS THE PRODUCT AND EXCLUSIVE PROPERTY OF MWT ARCHITECTURE. NEITHER THIS DOCUMENT NOR INFORMATION IS CONTAINED...