To Order Prints - www.ldirepro.com



## GENERAL NOTES:

PLAN NOTES:

1) CONTRACTOR SHALL VERIFY ALL DIMENSIONS AND LAYOUTS PRIOR TO CONSTRUCTION. SHOULD A DISCREPANCY BE ENCOUNTERED, THE ARCHITECT SHALL BE NOTIFIED IMMEDIATELY BEFORE COMMENCING WITH THE WORK.

2) CONTROL JOINTS IN CONCRETE SLABS ON GRADE SHALL BE SAWN. JOINT SHALL BE FILLED WITH BEAD OF JOINT FILLER. THIS JOINT SHALL BE 1/8" WIDE AND 1/5 THE DEPTH OF THE THICKNESS OF THE SLAB OR KEYED CONTROL JOINT. MAXIMUM SPACING SHALL BE 15'-0" O.C. IN EACH DIRECTION. CUT JOINTS WITHIN 12 HOURS OF DEPOSIT OF CONCRETE.

3) ALL CONSTRUCTION MATERIALS AND FASTENING SHALL COMPLY WITH WIND DESIGN CALCULATIONS.

SECTION NOTES:

1) GROUTED CONCRETE BLOCK CELLS SHALL BE FILLED WITH 3,000 PSI PEA GRAVEL CONCRETE WITH ONE #5 REBAR TIED TO STEEL IN FOOTING AND IN CONCRETE BOND BEAM. PROVIDE GROUTED CELLS @ 4'-0" O.C., AT BUILDING CORNERS, AT EACH SIDE OF DOOR AND WINDOW OPENINGS, AND ELSEWHERE AS SHOWN ON DRAWINGS.

2) PRE-ENGINEERED CONCRETE LINTELS INSTALLED OVER OPENINGS SHALL HAVE A MINIMUM OF 8" OF BEARING ON EACH SIDE. BEARING ENDS SHALL BE FILLED WITH 3,000 PSI PEA GRAVEL CONCRETE AND SHALL HAVE TWO #5 BARS CONTINUOUS FROM LINTEL TO FOOTING.

3) ALL CONSTRUCTION MATERIALS AND FASTENING SHALL COMPLY WITH WIND DESIGN CALCULATIONS.

STRUCTURAL NOTES:

1) DRAWINGS OF PRE-MANUFACTURED AND PRE-ENGINEERED TRUSSES ARE DIAGRAMATIC ONLY TO SHOW OUTLINE OF SPACES. THESE DRAWINGS DO NOT PURPORT TO SHOW ACTUAL CROSS MEMBERS OR BRACING THAT MAY BE REQUIRED.

2) CONTRACTOR, TRUSS MANUFACTURER AND HVAC CONTRACTOR SHALL COORDINATE TRUSS AND ROOF FRAMING WITH ALL DUCTWORK AND EQUIPMENT. ALLOW FOR CLEARANCES OF CONTINUOUS DUCT TRUNK LINES AS SHOWN ON THE DRAWINGS AS WELL AS ANY BLOCKING OR GIRDER TRUSSES TO ALLOW FOR DUCTWORK TO TURN TO AND FROM THE AIR HANDLER UNIT AND/OR OTHER DUCTS. NOTE THAT DUCT SIZES SHOWN ON THE HVAC DRAWINGS SHOULD BE INCREASED TO ALLOW FOR 2" OF INSULATION ALL AROUND.

3) TRUSS MANUFACTURER SHALL PROVIDE ATTIC, FLAT, SCISSOR, GIRDER, JACK, HIP OR OTHER TYPE TRUSSES AS REQUIRED. SPECIAL ATTENTION IS CALLED TO THE REFLECTED CEILING PLAN, ROOF PLAN AND HVAC DRAWINGS.

4) ANY ATTIC OR MECHANICAL SPACES SHALL PROVIDE A MINIMUM OF 30 PSF AUXILIARY LOAD IN ADDITION TO ANY MECHANICAL EQUIPMENT LOADS.

5) THESE DRAWINGS DO NOT SHOW FRAMING FOR DRYWALL CEILINGS OR SOFFITS. IT SHALL BE THE CONTRACTORS RESPONSIBILITY TO CALCULATE MATERIAL AND LABOR TO PERFORM THIS WORK. SPECIAL ATTENTION IS CALLED TO WALL SECTIONS FOR PLATE HEIGHTS, BUILDING SECTIONS, REFLECTED CEILING PLANS AND FINISH SCHEDULES.

6) PRE-ENGINEERED TRUSS MANUFACTURER SHALL SUPPLY SHOP DRAWINGS WITH LIVE AND DEAD LOAD COMPLIANCE SEALED AND CERTIFIED BY AN ENGINEER LICENSED IN THE STATE OF FLORIDA.

7) ALL STRUCTURAL LUMBER USED FOR HEADERS, BEAMS OR OTHER BLOCKING OR FRAMING SHALL HAVE A MINIMUM BENDING STRESS OF 1,450 PSI UNLESS OTHERWISE NOTED. (FOR EXAMPLE: NO. 1 DENSE SOUTHERN PINE OR NO. 2 DENSE DOUGLAS FIR-LARCH).

8) ALL CONSTRUCTION MATERIALS AND FASTENING SHALL COMPLY WITH WIND DESIGN CALCULATIONS.

MECHANICAL NOTES:

1) CONTRACTOR, TRUSS MANUFACTURER AND HVAC CONTRACTOR SHALL COORDINATE TRUSS AND ROOF FRAMING WITH ALL DUCTWORK AND EQUIPMENT. ALLOW FOR CLEARANCES OF CONTINUOUS DUCT TRUNK LINES AS SHOWN ON THE DRAWINGS AS WELL AS ANY BLOCKING OR GIRDER TRUSSES TO ALLOW FOR DUCTWORK TO TURN TO AND FROM THE AIR HANDLER UNIT AND/OR OTHER DUCTS. NOTE THAT DUCT SIZES SHOWN ON THE HVAC DRAWINGS SHOULD BE INCREASED TO ALLOW FOR 2" OF INSULATION ALL AROUND.

2) PROVIDE AND INSTALL A ONE-HOUR RATED FIRE DAMPER IN ALL DUCTS WHICH PENETRATE A ONE-HOUR WALL. PROVIDE AN ACCESS DOOR WITH EACH FIRE DAMPER TO FACILITATE CHANGING OF FUSIBLE LINK.

# PROPOSED RENOVATIONS

# TO THE

# PUTNAM COUNTY GOVERNMENTAL COMPLEX

# AT

# Crill Ave & Westover Dr
# PALATKA, FLORIDA

## ABBREVATIONS:

| | | | |
|---|---|---|---|
| AFF | ABOVE FINISHED FLOOR | LBL | LABEL |
| AG | ABOVE GROUND | LAB | LABORATORY |
| ACOUS | ACOUSTICAL | LAV | LAVATORY |
| ADD | ADDITIVE | LT | LIGHT |
| A/C | AIR CONDITIONING | LTL | LINTEL |
| ALT | ALTERNATE | LL | LIVE LOAD |
| AL | ALUMINUM | LVR | LOUVER |
| ANO | ANODIZED | | |
| ARCH | ARCHITECT | MH | MANHOLE |
| ASPH | ASPHALT | MFR | MANUFACTURE OR MANUFACTURER |
| | | MAS | MASONRY |
| BM | BENCH MARK | MO | MASONRY OPENING |
| BLKG | BLOCKING | MTRL | MATERIAL OR MATERIALS |
| BOT | BOTTOM | MAX | MAXIMUM |
| BRK | BRICK | MECH | MECHANICAL |
| BLDG | BUILDING | MTL | METAL |
| BUR | BUILT UP ROOFING | MIN | MINIMUM |
| | | MISC | MISCELLANEOUS |
| CAB | CABINET | MLD | MOLDING OR MOULDING |
| CB | CATCH BASIN | MT | MOUNT, MOUNTED OR MOUNTING |
| CLG | CEILING | MULL | MULLION |
| ℄ | CENTERLINE | | |
| CT | CERAMIC TILE | NOM | NOMINAL |
| CIR | CIRCLE | NIC | NOT IN CONTRACT |
| CO | CLEAN OUT (SEWER) | NTS | NOT TO SCALE |
| CLR | CLEAR | | |
| CONC | CONCRETE | OC | ON CENTER OR ON CENTERS |
| CMU | CONCRETE MASONRY UNIT | OPNG | OPENING |
| CONST | CONSTRUCTION | OD | OUTSIDE DIAMETER |
| CONT | CONTINUOUS OR CONTINUE | OA | OVERALL |
| CONTR | CONTRACT OR CONTRACTOR | OH | OVERHEAD |
| CJT | CONTROL JOINT | | |
| CU | COPPER | | |
| CMP | CORRUGATED METAL PIPE | PNT | PAINT OR PAINTED |
| CTR | COUNTER | PNL | PANEL |
| C&G | CURB & GUTTER | PAR | PARALLEL |
| | | PVMT | PAVEMENT |
| DL | DEAD LOAD | PLAS | PLASTER |
| DEMO | DEMOLISH OR DEMOLITION | PLAS LAM | PLASTIC LAMINATE |
| DTL | DETAIL | PL | PLATE |
| DIA | DIAMETER | PLYWD | PLYWOOD |
| DIM | DIMENSION | PVC | POLYVINYL CHLORIDE |
| DR | DOOR | PIP | POUR-IN-PLACE CONCRETE |
| DS | DOWNSPOUT | PP | POWER POLE |
| DWG | DRAWING | PL | PROPERTY LINE |
| D/W | DRIVEWAY | | |
| | | RAD | RADIUS |
| ESMT | EASEMENT | REFR | REFRIGERATOR |
| ELEC | ELECTRIC OR ELECTRICAL | REINF | REINFORCE, REINFORCED OR |
| EL | ELEVATION | | REINFORCING |
| EMER | EMERGENCY | RCP | REINFORCED CONCRETE PIPE |
| EQ | EQUAL | REM | REMOVE |
| EXIST | EXISTING | REQ'D | REQUIRED |
| EXT | EXTERIOR | RA | RETURN AIR |
| | | REV | REVISION, REVISED OR |
| FD | FACE OF FINISH | | REVISES |
| FOC | FACE OF CONCRETE | ROW | RIGHT OF WAY |
| FOB | FACE OF BRICK | RD | ROOF DRAIN |
| FOM | FACE OF MASONRY | RM | ROOM |
| FOS | FACE OF STUDS | RO | ROUGH OPENING |
| FF | FACTORY FINISH | | |
| FAS | FASTEN OR FASTENER | SS | SANITARY SEWER |
| FG | FIBERGLASS | SCH | SCHEDULE |
| FIN | FINISH | SECT | SECTION |
| FFE | FINISH FLOOR ELEVATION | SHT | SHEET |
| FE | FIRE EXTINGUISHER | SH | SHELF OR SHELVING |
| FEC | FIRE EXTINGUISHER CABINET | SIM | SIMILAR |
| FH | FIRE HYDRANT | SC | SOLID CORE |
| FP | FIRE PROOF OR FIRE PROOFING | SPK | SPEAKER |
| FRT | FIRE-RETARDANT | SPEC | SPECIFICATION OR SPECIFICATIONS |
| FLG | FLASHING | SQ | SQUARE |
| FLR | FLOOR OR FLOORING | SST | STAINLESS STEEL |
| FLCO | FLOOR CLEANOUT | STD | STANDARD |
| FD | FLOOR DRAIN | STL | STEEL |
| FLDR | FLUORESCENT | STOR | STORAGE |
| FW | FLUSH WOOD | SD | STORM DRAIN |
| FTG | FOOTING | STR | STRUCTURAL |
| FND | FOUNDATION | SCT | STRUCTURAL CLAY TILE |
| | | SUS | SUSPENDED |
| | | SYS | SYSTEM |
| GA | GAGE OR GAUGE | | |
| GALV | GALVANIZE | TEL | TELEPHONE |
| GC | GENERAL CONTRACT OR | THK | THICK OR THICKNESS |
| | GENERAL CONTRACTOR | THR | THRESHOLD |
| GL | GLASS OR GLAZING | TBR | TO BE REMOVED |
| GB | GRAB BAR | TOS | TOP OF STEEL |
| GD | GRADE OR GRADING | TW | TOP OF WALL |
| GYPBD | GYPSUM BOARD | TYP | TYPICAL |
| | | UC | UNDERCUT |
| HDWR | HARDWARE | UG | UNDERGROUND |
| HDR | HEADER | UNO | UNLESS |
| HTG | HEATING | | |
| HVAC | HEATING/VENTILATING/ | VB | VAPOR BARRIER |
| | AIR CONDITIONING | VERT | VERTICAL |
| HT | HEIGHT | VIN | VINYL |
| HC | HOLLOW CORE | VCT | VINYL COMPOSITION TILE |
| HM | HOLLOW METAL | VCP | VITRIFIED CLAY PIPE |
| HOR | HORIZONTAL | | |
| HB | HOSE BIBB | | |
| | | WSCT | WAINSCOT |
| INCL | INCLUDE, INCLUDED, OR INCLUDING | WH | WATER HEATER |
| INV | INVERT ELEVATION | WC | WATER CLOSET |
| ID | INSIDE DIAMETER | WP | WATERPROOFING |
| INT | INTERIOR | WWF | WELDED WIRE FABRIC |
| | | W/ | WITH |
| | | W/OUT | WITHOUT |
| JT | JOINT | WD | WOOD |
| KPL | KICKPLATE | | |
| KIT | KITCHEN | | |

## SHEET INDEX:


| SHT No. | DESCRIPTION |
|---|---|
| A0.0 | COVER (THIS SHEET) |
| C0.1 | PARTIAL SITE PLAN |
| C0.1A | PARTIAL SITE PLAN W/ ADD. ALT. |
| C0.2 | PARTIAL SITE PLAN |
| C0.3 | PARTIAL GRAD SITE PLAN |
| C0.3.1 | PARTIAL GRAD SITE PLAN |
| C0.4 | SITE DETAILS |
| C0.5 | SITE DETAILS |
| C0.6 | SITE DETAILS |
| L1.1 | PARTIAL LANDSCAPING PLAN |
| L1.2 | PARTIAL LANDSCAPING PLAN |
| L2.1 | PARTIAL LANDSCAPING PLAN |
| L3.1 | IRRIGATION PLAN & DETAILS |
| L3.2 | IRRIGATION PLAN & DETAILS |
| L3.3 | IRRIGATION PLAN & DETAILS |
| L3.4 | IRRIGATION PLAN & DETAILS |
| E1.01 | General Notes & Symbolsmy |
| E1.02 | Typical Foundation Details |
| E1.03 | Typical Roof Details |
| E1.04 | Typical Roof Details |
| E1.05 | Typical Roof Details |
| E1.06 | Typical Roof Details |
| E1.07 | Typical Roof Details |
| E1.08 | Typical Roof Details |
| E2.01 | Foundation Plan |
| E2.02 | Foundation Plan |
| E2.03 | Foundation Plan |
| E3.01 | Framing Plan |
| E3.02 | Framing Plan |
| E3.03 | Framing Plan |
| A0.1 | OVERALL BUILDING FLOOR PLAN |
| A0.2 | PROPOSED FACADE PLANS & ELEVATIONS |
| A0.3 | PROPOSED FACADE PLANS & ELEVATIONS |
| A0.4 | FACADE SECTIONS & DETAILS |
| A0.5 | FACADE SECTIONS & DETAILS |
| A0.6 | FACADE SECTIONS & DETAILS |
| A0.7 | FACADE SECTION & DETAILS |
| A0.8 | CANOPY PLAN & ELEVATION |
| A1.1 | BUILDING "A" DEMOLITION PLAN |
| A1.1.1 | BUILDING "A" ELEV DEMOLITION PLAN |
| A1.2 | BUILDING "A" FLOOR PLAN |
| A1.2.1 | BUILDING "A" FLOOR PLAN PLAN & SECTION |
| A1.3 | BUILDING "A" ROOF PLAN |
| A1.4 | BUILDING "A" ROOF SECTIONS & DETAILS |
| A1.5 | BUILDING "A" INTERIOR ELEVATIONS & SECTIONS |
| A1.5.1 | BUILDING "A" INTERIOR ELEVATIONS & SECTIONS |
| A1.6 | BUILDING "A" STOREFRONT ELEVATIONS & SECTIONS |
| A2.1 | BUILDING "B" DEMOLITION PLAN |
| A2.2 | BUILDING "B" FLOOR PLAN |
| A2.2.1 | BUILDING "B" ENLARGED FLOOR PLANS |
| A2.3 | BUILDING "B" ROOF PLAN |
| A2.4 | BUILDING "B" ROOF SECTIONS & DETAILS |
| A2.5 | BUILDING "B" INTERIOR ELEVATIONS & SECTIONS |
| A2.5.1 | BUILDING "B" INTERIOR ELEVATIONS & SECTIONS |
| A2.6 | BUILDING "B" STOREFRONT ELEVATIONS & SECTIONS |
| A3.1 | BUILDING "C" DEMOLITION PLAN |
| A3.2 | BUILDING "C" FLOOR PLAN |
| A3.2.1 | BUILDING "C" ENLARGED FLOOR PLANS |
| A3.3 | BUILDING "C" ROOF PLAN |
| A3.4 | BUILDING "C" ROOF SECTIONS & DETAILS |
| A3.5 | BUILDING "C" INTERIOR ELEVATIONS & SECTIONS |
| A3.6 | BUILDING "C" STOREFRONT ELEVATIONS & SECTIONS |
| A3.8 | BUILDING "D" STOREFRONT ELEVATIONS & SECTIONS |
| A3.8.1 | BUILDING "D" STOREFRONT ELEVATIONS & SECTIONS |
| A4.1 | BUILDING "E, D, & C" DEMOLITION PLAN |
| A4.2 | BUILDING "E, D, & C" FLOOR PLAN |
| A4.2.1 | BUILDING "E, D, & C" ENLARGED FLOOR PLANS |
| A4.3 | BUILDING "E, D, & C" ROOF PLAN |
| A4.4 | BUILDING "E, D, & C" ROOF SECTIONS & DETAILS |
| A4.5 | BUILDING "E, D, & C" INTERIOR ELEVATIONS & SECTIONS |
| A4.6 | BUILDING "E, D, & C" STOREFRONT ELEVATIONS & SECTIONS |
| A7.1 | BUILDING "F" DEMOLITION PLAN |
| A7.2 | BUILDING "F" FLOOR PLAN |
| A7.2.1 | BUILDING "F" ENLARGED FLOOR PLANS |
| A7.3 | BUILDING "F" ROOF PLAN |
| A7.4 | BUILDING "F" ROOF SECTIONS & DETAILS |
| A7.5 | BUILDING "F" INTERIOR ELEVATIONS & SECTIONS |
| A7.6 | BUILDING "F" STOREFRONT ELEVATIONS & SECTIONS |
| A7.6.1 | BUILDING "F" STOREFRONT ELEVATIONS & SECTIONS |
| M0.1 | OVERALL MECHANICAL ROOF PLAN |
| M1.1 | BLDG A - HVAC PLAN |
| M1.2 | BLDG B - HVAC PLAN |
| M1.3 | BLDG C - HVAC PLAN |
| M1.4 | BLDG DAC - HVAC PLAN |
| M1.5 | BLDG DAC - HVAC PLAN |
| M1.6 | HVAC EQUIPMENT SCHEDULES |
| M1.7 | HVAC DETAILS |
| E0.1 | ELECTRICAL SITE PLAN |
| E1.1 | BLDG A LIGHTING PLAN |
| E1.2 | BLDG A POWER PLAN |
| E1.3 | BLDG A LIGHTING PLAN |
| E2.2 | BLDG B POWER PLAN |
| E2.3 | BLDG B LIGHTING PLAN |
| E3.2 | BLDG C POWER PLAN |
| E3.3 | BLDG C LIGHTING PLAN |
| E4.1 | BLDG DAC POWER PLAN |
| E5.1 | ELECTRICAL RISER DIAGRAMS |
| E6.1 | ELECTRICAL PANEL SCHEDULES |
| E6.2 | ELECTRICAL PANEL SCHEDULES |
| E6.3 | ELECTRICAL PANEL SCHEDULES |
| E6.4 | ELECTRICAL PANEL SCHEDULES |
| P0.1 | PLUMBING SITE PLAN |
| P1.1 | BLDG A PLUMBING PLANS |
| P2.1 | BLDG B SANITARY PLAN |
| P2.2 | BLDG B WATER SUPPLY PLAN |
| P3.1 | BLDG C SANITARY PLAN |
| P3.2 | BLDG C WATER SUPPLY PLAN |
| P4.1 | BLDG DAC PLUMBING PLAN |
| P7.1 | BLDG DAC PLUMBING PLAN |
| P8.1 | RISER DIAGRAMS - SANITARY |
| P8.2 | RISER DIAGRAMS - SANITARY |
| P9.1 | RISER DIAGRAMS - SUPPLY |
| P9.2 | RISER DIAGRAMS - SUPPLY |
| FA 1.1 | BLDG A - FIRE ALARM PLAN |
| FA 2.1 | BLDG B - FIRE ALARM PLAN |
| FA 3.1 | BLDG C - FIRE ALARM PLAN |
| FA 4.1 | BLDG DAC - FIRE ALARM PLAN |
| FA 5.1 | BLDG DAC - FIRE ALARM PLAN |
| FA 6.1 | FIRE ALARM RISER DIAGRAMS |
| FSP 0.1 | FIRE SPRINKLER SITE PLAN |
| FSP 1.1 | FIRE SPRINKLER BLDG A |
| FSP 2.1 | FIRE SPRINKLER BLDG B |
| FSP 3.1 | FIRE SPRINKLER BLDG C |
| FSP 4.1 | FIRE SPRINKLER BLDG D & E |
| FSP 7.1 | FIRE SPRINKLER BLDG D & E |


## LOCATION MAP:

A0.0_COVER.dwg

SKINNER VIGNOLA McLEAN, INC.
ARCHITECTS & PLANNERS
1628 N. W. 6th Street
Gainesville, Florida 32609
Florida Certificate No. AA3478
(352) 378-4400
FAX (352) 377-5378

RENOVATIONS FOR THE
PUTNAM COUNTY
GOVERNMENTAL COMPLEX
PALATKA, FL
SVM #00505

Howard J. McLean, Jr.
License #0001132

DATE: 04/25/07
DRAWN BY: D.A.M.
CHECKED BY: H.J.M.
REVISIONS:

COVER SHEET 7

SHEET A0.0 OF

RENOVATIONS TO P.C. GOV. COMPLEX