GENERAL CONSTRUCTION REQUIREMENTS

1. ALL WORK SHALL BE DONE IN A SAFE AND WORKMANLIKE MANNER AND IN STRICT ACCORDANCE WITH THE LOCAL GOVERNING BUILDING CODE, NATIONAL ELECTRIC CODE, AND ALL APPLICABLE REGULATIONS AND ORDINANCES HAVING JURISDICTION.
2. THE CONTRACTOR SHALL THOROUGHLY EXAMINE ALL FACTORS REASONABLY AVAILABLE TO HIM, INCLUDING BUT NOT LIMITED TO, THE DRAWINGS, PROJECT MANUAL, INCLUDING SPECIFICATIONS, SOIL REPORT, SITE SURVEY WITH BOUNDARY AND TOPOGRAPHIC DETAIL, AND OTHER CONDITIONS TOTAL INFORMATION REGARDING SITE HISTORY AND SEASONAL WEATHER CONDITIONS. SOIL REPORT DATA MAY NOT BE ALL INCLUSIVE AND IT IS THE CONTRACTOR'S RESPONSIBILITY TO FURTHER INVESTIGATE SUBSURFACE CONDITIONS AS HE DETERMINES NECESSARY. ANY CONSTRUCTION PERFORMED BY THE CONTRACTOR ON AN EXISTING BUILDING NOT PREPARED BY OTHERS WILL CONSTITUTE ACCEPTANCE OF THE FACT.
3. EACH SUBCONTRACTOR IS RESPONSIBLE FOR HAVING A THOROUGH KNOWLEDGE OF ALL DRAWINGS AND SPECIFICATIONS IN THEIR RELATED FIELD. THE FAILURE TO ACQUAINT OURSELF WITH THIS KNOWLEDGE DOES NOT RELIEVE HIM OF ANY RESPONSIBILITY FOR PERFORMING HIS WORK PROPERLY. NO ADDITIONAL COMPENSATION SHALL BE ALLOWED BECAUSE OF CONDITIONS THAT OCCUR DUE TO FAILURE TO FAMILIARIZE WORKERS WITH THIS KNOWLEDGE.
4. VERIFY ALL DIMENSIONS IN THE FIELD PRIOR TO FABRICATION OF STRUCTURAL ITEMS. IF ANY DISCREPANCIES ARE FOUND BETWEEN WHAT IS SHOWN ON THE PLANS AND WHAT EXISTS IN THE FIELD, CONTACT THE WAL-MART CONSTRUCTION MANAGER TO DETERMINE WHAT SHOULD BE DONE. DO NOT CHANGE EXISTING CONDITIONS AS REQUIRED BEGINNING OF STEEL FABRICATION, MEANS ACCEPTANCE OF EXISTING CONDITIONS.
5. WAL-MART SHALL OCCUPY THE BUILDING DURING CONSTRUCTION. THE CONTRACTOR SHALL COORDINATE WITH WAL-MART ALL CONSTRUCTION PROCEDURES WHICH WILL INTERFERE WITH THE NORMAL DAILY OPERATIONS OF THE STORE. THE CONTRACTOR SHALL OBTAIN PERMISSION FROM WAL-MART FOR ALL INTERRUPTIONS OF WAL-MART SERVICES TO THE EXISTING BUILDING PRIOR TO THE INTERRUPTION. ACCIDENTAL INTERRUPTIONS SHALL BE REPAIRED IMMEDIATELY WITH APPROPRIATE FORCES.
6. THE EXISTING BUILDING SHALL BE PROTECTED AT ALL TIMES FROM MOISTURE, DUST AND DEBRIS. INSTALL DUST PARTITIONS AS REQUIRED AND/OR AS SHOWN TO KEEP THE EXISTING PREMISES FREE FROM DUST AND DEBRIS. PROVIDE BARRICADES SEPARATING THE PUBLIC FROM CONSTRUCTION ACTIVITY.
7. ANY DAMAGE TO WAL-MART'S PROPERTY CAUSED BY THE CONSTRUCTION PROCESS SHALL BE REPAIRED/REPLACED AT NO ADDITIONAL COST TO WAL-MART. THIS INCLUDES ALL MERCHANDISE. THE CONTRACTOR SHALL REIMBURSE WAL-MART FOR ALL DAMAGED MERCHANDISE.
8. THE CONTRACTOR SHALL MAINTAIN THE INTEGRITY OF THE EXISTING BUILDING SECURITY AT ALL TIMES. THIS INCLUDES KEEPING THE BUILDING SECURE FROM PERSONS, MATERIALS, EQUIPMENT, OR HAZARDS. THE CONTRACTOR SHALL BE RESPONSIBLE TO MAINTAIN THE INTEGRITY OF ALL EXISTING SECURITY SYSTEMS. THE CONTRACTOR SHALL OBTAIN PERMISSION FROM WAL-MART CONSTRUCTION MANAGER PRIOR TO THE MODIFICATION OF ANY SECURITY SYSTEM OR THE DISARMING OF SUCH. IF REQUIRED, PROVIDE A BONDED SECURITY GUARD AT CONTRACTOR'S EXPENSE TO MAINTAIN SECURITY OF THE STORE.
9. THE CONTRACTOR SHALL KEEP THE CONSTRUCTION AREA FREE AND CLEAR OF DEBRIS. REMOVE TRASH AND DEBRIS FROM CONSTRUCTION AREA AND DO NOT ALLOW TO ACCUMULATE. NO FLAMMABLE MATERIALS/LIQUIDS MAY BE STORED IN THE BUILDING. THE BUILDING IS EXPANSIVE DURING CONSTRUCTION. PROVIDE EXTINGUISHERS AS REQUIRED BY LOCAL AND STATE AUTHORITIES. DO LISTED CARBON DIOXIDE CHEMICAL FIRE EXTINGUISHERS, ACCESSIBLE AT ALL TIMES WITHIN ALL CONSTRUCTION AREAS.
10. A TYPE OF POSSESSION WAL-MART'S PROVIDED FIRE EXTINGUISHERS IN ACCORDANCE WITH NFPA 10, ONE 2A-10 B/C RATED EXTINGUISHER WILL BE PROVIDED FOR EACH 3000 SF AND LOCATED SO THAT TRAVEL DISTANCE TO THE CLOSEST FIRE EXTINGUISHER IS NO MORE THAN 75 FEET. FINAL FIRE EXTINGUISHER LOCATIONS ARE TO BE APPROVED BY THE FIRE MARSHAL.
11. THE CONTRACTOR SHALL MAINTAIN THE REQUIRED NUMBER OF EXITS FROM THE STORE. MAINTAIN EXITS, EXIT SIGNS AND EMERGENCY LIGHTING AT ALL TIMES AS REQUIRED BY THE GOVERNING AUTHORITIES.
12. COORDINATE CONSTRUCTION SEQUENCING WITH WAL-MART CONSTRUCTION MANAGER AND PHASING SCHEDULE PROVIDED BY WAL-MART, BASED ON THIS PHASING SCHEDULE, DEVELOP A SCHEDULE OF WORK INDICATING THE STARTING AND COMPLETION DATES OF THE DIFFERENT PHASES OF THIS PROJECT. SUBMIT THE SCHEDULE TO WAL-MART FOR APPROVAL WITHIN TEN (10) DAYS PRIOR TO THE SIGNING OF THE CONTRACT. WAL-MART RESERVES THE RIGHT TO REVISE THIS SCHEDULE "TO BEST MEET THEIR NEEDS FOR STORE OPERATIONS AT NO ADDITIONAL COST TO WAL-MART. AS THE CONSTRUCTION PROGRESSES, UPDATE WORK SCHEDULE IN WRITING TO THE STORE MANAGER AND CONSTRUCTION MANAGER EVERY 4 WEEKS (OR AS NEEDED TO MAINTAIN STORE OPERATIONS).
13. REMOVE ANY EXISTING ITEMS, SERVICES, FINISHES/OR SURFACES AS REQUIRED FOR THE INSTALLATION OF NEW CONSTRUCTION. PROVIDE PATCHING FOR NEW CONDUITS AND PIPING, SHOWN OR NOT, AND FINISH CUT PATCHES TO MATCH ADJACENT EXISTING FINISHES.
14. REPAIR, RE-ROUTE AND EXTEND ALL SERVICES, PIPING, CONDUIT OF EXISTING ITEMS AND EQUIPMENT AS REQUIRED DURING THE CONSTRUCTION PROCESS FOR THE COMPLETE INSTALLATION AND OPERATIONS OF NEW EQUIPMENT. THIS INCLUDES ALL ITEMS SHOWN OR NOT SHOWN ON THE DRAWINGS. RESET EXISTING EQUIPMENT OR RELOCATE ITEMS AS REQUIRED FOR PROPER OPERATION.
15. PATCH, REPAIR, AND REFINISH CONSTRUCTION AT INTERFACE OF NEW AND EXISTING FINISHES. FINISH NEW SURFACES AT INTERFACE TO MATCH EXISTING.
16. ALL QUESTIONS RELATING TO THE CONSTRUCTION OF THIS PROJECT SHALL BE DONE IN WRITTEN FORM USING THE "REQUEST FOR INFORMATION" FORM, INCLUDED IN THE SPECIFICATIONS, THROUGH THE GENERAL CONTRACTOR ONLY. FOLLOW INSTRUCTIONS WHEN COMPLETING AND SENDING THIS FORM.

GENERAL SITE VERIFICATION REQUIREMENTS

1. EXISTING CONDITIONS SHOWN IN THESE PLANS ARE FROM LIMITED FIELD OBSERVATIONS BY THE ARCHITECT AND ORIGINAL DESIGN DRAWINGS. EXISTING MATERIAL DIMENSIONS, ELEVATIONS, AND GENERAL CONDITIONS OF THE BUILDING SHALL BE VERIFIED BEFORE PURCHASE OF MATERIAL OR CONSTRUCTION. NOTIFY WAL-MART CONSTRUCTION MANAGER OF ANY DISCREPANCIES BETWEEN PLANS AND FIELD CONDITIONS IMMEDIATELY.
2. ALL UTILITY LOCATIONS SHOWN ARE APPROXIMATE. THE CONTRACTOR SHALL FIELD VERIFY THE EXACT LOCATION OF ALL EXISTING UTILITIES (WHETHER SHOWN OR NOT) PRIOR TO THE SUBMISSION OF HIS BIDDING. THE COMMENCEMENT OF CONSTRUCTION, THE CONTRACTOR SHALL NOTIFY THE WAL-MART CONSTRUCTION MANAGER OF THE DISCOVERY OF EXISTING UTILITIES NOT SHOWN OR NOTED ON DRAWINGS. CONTRACTOR SHALL VERIFY EXACT LOCATIONS AND DEPTHS OF INVERTS AND LIFT STATIONS PRIOR TO ANY EXCAVATION.
3. THE CONTRACTOR SHALL VERIFY ALL GRADES AND PROVIDE FINAL GRADES. IF RAMPS, STOOPS, FIXTURES ARE INSTALLED VERY FINAL GRADES SURROUNDING THE NEW CONSTRUCTION AND ADJUST STOOP HEIGHTS, RAMP LENGTHS, ETC. TO ACCOMMODATE REQUIRED RAMP SLOPE OR PRIER HEIGHTS. ALL RAMPS MUST BE TO WAL-MART AND A LOCAL LANDICAP ACCESSIBILITY REQUIREMENTS. IF THERE IS A CONFLICT IN FIELD CONDITIONS, NOTIFY WAL-MART CONSTRUCTION MANAGER PRIOR TO CONSTRUCTION OF ORDERING OF MATERIALS.
4. CONTRACTOR SHALL VERIFY EXISTING FINISH FLOOR ELEVATION AT THE NEW OPENING OF THE EXISTING BUILDING PRIOR TO ESTABLISHING THE FINISH FLOOR ELEVATION. THE CONTRACTOR SHALL VERIFY EXISTING FOUNDATION DEPTHS TO ENSURE PROPER BLOCK COURSING. ANY DISCREPANCY SHALL BE REPORTED TO THE WAL-MART CONSTRUCTION MANAGER AND THE ARCHITECT PRIOR TO CONSTRUCTION.

GENERAL SITE PLAN NOTES

REFER TO SHEET SP1

1. POWER WASH (CLEAN) EXISTING SIDEWALKS AND GARDEN CENTER SLAB TO REMOVE STAINS, CHEWING GUM AND DIRT. THIS CLEANING SHALL BE EXECUTED 3 DAYS PRIOR TO RE-GRAND OPENING. COORDINATE WITH WAL-MART CONSTRUCTION MANAGER.
2. NEW SIDEWALKS AND FLATWORK SHOWN ON THE DRAWINGS SHALL BE 4" THICK WITH LIGHT BROOM FINISH. TOOL ALL CONCRETE EDGES IN CONTACT WITH EXPANSION JOINTS AND BUILDING SURFACES. SLOPE CONCRETE 2% AWAY FROM BUILDING OR AS SHOWN ON THE DRAWINGS. CROSS SLOPE OF ALL SIDEWALKS SHALL BE MAXIMUM 2% SLOPE. PAINT THE EXISTING AND NEW SIDEWALK CURB 6" ON TOP AND FACE.
3. CONCRETE FINISH AT DETECTABLE WARNING AREAS SHALL BE COLORED STAMPED CONCRETE IMPRINT PATTERN. REFER TO SPECIFICATIONS.
4. RAKE EXISTING SIDEWALK CONTROL JOINTS AND JOINTS BETWEEN SIDEWALK AND BUILDING. INSTALL NEW SEALANT AT ALL EXISTING SIDEWALK CONTROL JOINTS AND EXPANSION JOINTS.
5. RUBBED CONCRETE FINISH AT ALL EXPOSED VERTICAL SURFACES AT CONCRETE RETAINING WALLS AND FOUNDATIONS.

GENERAL DEMOLITION REQUIREMENTS

REFER TO SHEET D1

1. ALL DEMOLITION SHALL BE CARRIED OUT IN A SAFE MANNER AND IN STRICT ACCORDANCE WITH STATE REGULATIONS.
2. THE CONTRACTOR SHALL FIELD VERIFY THE EXTENT OF DEMOLITION. THE WORK INCLUDES, BUT IS NOT LIMITED TO, THE DEMOLITION AND REMOVAL OF WALLS, DOORS, FIXTURES, PLUMBING, MECHANICAL AND ELECTRICAL ITEMS INCLUDING CONDUITS AND INCIDENTALS AS SHOWN ON DRAWINGS OR AS REQUIRED FOR THE INSTALLATION OF THE NEW WORK FOR A COMPLETE JOB. THE CONTRACTOR SHALL REPLACE ANY/ALL FLOOR, WALL, OR CEILING FINISHES DAMAGED AS A RESULT OF DEMOLITION. MATCH EXISTING ADJACENT FINISHES.
3. WHEN CEILINGS ARE REMOVED, CAP AND SEAL A MINIMUM OF 8' BELOW FINISH FLOOR OR A MINIMUM OF 8" ABOVE FINISH CEILING.
4. IT IS THE CONTRACTOR'S RESPONSIBILITY TO PROVIDE ADEQUATE SHORING, BRACING AND SUPPORT SYSTEMS FOR EXISTING STRUCTURE AND TO KEEP THE EXISTING STRUCTURE INTACT AND IN A SAFE CONDITION DURING DEMOLITION AND NEW CONSTRUCTION. THE CONTRACTOR SHALL RETAIN A REGISTERED PROFESSIONAL ENGINEER TO DESIGN THE SHORING OR BRACING AND SPECIFY DEMOLITION PROCEDURES. IT IS THE CONTRACTOR'S RESPONSIBILITY FOR MEANS AND METHODS OF DEMOLITION AND NEW CONSTRUCTION.
5. PRIOR TO THE EXCAVATION OF FOUNDATIONS ADJACENT TO THE EXISTING STRUCTURE, PROVIDE ADEQUATE SUPPORT FOR THE SUB-BASE TO PREVENT UNDERMINING OF EXISTING BUILDING.
6. DURING DEMOLITION AND RECONSTRUCTION, THE CONTRACTOR SHALL COORDINATE WITH THE WAL-MART CONSTRUCTION MANAGER ANY REQUIRED SAFETY BARRIERS OR DARK CADES. PROVIDE DARK CADES SO AS TO PREVENT INTRUSION OF PUBLIC INTO CONSTRUCTION AREAS.
7. REFER TO WAL-MART SCHEDULE CONSTRUCTION PHASING SCHEDULE FOR PHASING OF DEMOLITION AND NEW CONSTRUCTION. COORDINATE DEMOLITION WITH NEW CONSTRUCTION IN ORDER THAT THE STORE WILL HAVE UNINTERRUPTED WATER, SEWER, ELECTRICAL, GAS AND FIRE PROTECTION SERVICE.
8. REMOVE ONLY AS MUCH EXTERIOR WALL AS CAN BE MADE WEATHERTIGHT IN ONE WORKING DAY. THE NEW ROOF SYSTEM AT A RATE THAT CAN BE MADE WEATHERTIGHT IN ONE WORKING DAY. THE EXISTING EXTERIOR WALL ADJACENT TO THE EXPANSION AREA SHALL REMAIN UNTIL THE NEW CONSTRUCTION IS COMPLETE, SECURE, AND WEATHERTIGHT. THE DEMOLITION OF EXTERIOR WALLS SHALL BE DONE IN PHASES.
9. WHEN INSTALLING ROOF JOISTS EXPANSION THROUGH EXISTING MASONRY WALLS, REMOVE ONLY ENOUGH MASONRY AS REQUIRED TO INSTALL EXTENSION. CLOSE OPENING AT WALL AND ROOF SO AS TO PRECLUDE INFILTRATION OF MOISTURE INTO BUILDING.
10. ALL DEMOLITION MATERIALS NOT SALVAGED BY WAL-MART SHALL BE REMOVED BY THE CONTRACTOR. COORDINATE WITH WAL-MART CONSTRUCTION MANAGER REGARDING MATERIALS TO BE SALVAGED BY WAL-MART. REFER ALSO TO SPECIFICATIONS FOR SALVAGED ITEMS.
11. COORDINATE ALL TEMPORARY CONSTRUCTION WITH WAL-MART CONSTRUCTION MANAGER. REFER TO SHEET C1 FOR TEMPORARY DUST PARTITION LOCATIONS AND SPECIFICATIONS. PROVIDE DUST PARTITIONS PRIOR TO BEGINNING DEMOLITION. RELOCATE EXISTING SALES WALL SHELVING STANDARD FROM THE WALL BEING DEMOLISHED TO THE TEMPORARY DUST PARTITION. PROVIDE ADEQUATE BRACKING AND BRACING FOR SUPPORT OF SHELVING AND MERCHANDISE. DO NOT USE TEMPORARY DUST PARTITION AS BRACING AND/OR BRACING OF EXISTING BUILDING COMPONENTS. BRACE DUST PARTITIONS SO AS TO PREVENT THEM FROM MOVEMENT OR OBSTRUCTION.
12. NOT USED.
13. CONSTRUCT DUST PARTITIONS A MAXIMUM 6'-0" FROM VESTIBULE WALL AND 4'-0" FROM ALL OTHER WALLS. CONSTRUCT A MAXIMUM OF 40'-0" OF TEMPORARY DUST WALL IN 8 HOUR PERIOD.
14. ALL DUST PARTITIONS SHALL HAVE SINGLE ACTING DOORS OPENING OUT WITH CLOSERS. DOORS NO AGAINST CASELLO INDICATES IN OVERALL INCLUDE PASSAGE OF AIR DUST AND MOISTURE. PROVIDE MATS AT DOORS TO REDUCE TRACKING OF DUST, REPLACE OR CLEAN DAILY.
15. SEAL PERIMETER OF DUST PARTITIONS AND DOORS TO PREVENT PASSAGE OF DUST. TAPE JOINTS, DEPRESSIONS, JOINTS BETWEEN PANELS AND JOINTS BETWEEN PANELS AND DOORS, CEILING AND COLUMNS WITH 2" IN WIDE PRESSURE SENSITIVE TAPE.
16. REMOVE ALL CARPET COLUMN WRAPS.
17. REMOVE EXISTING RESILIENT FLOORING SYSTEM IN EXISTING BUILDING FLOOR AREAS AND PREPARE CONCRETE SUBSTRATE FOR NEW FLOORING SYSTEM.
18. REFER TO STRUCTURAL, MECHANICAL AND ELECTRICAL DRAWINGS FOR NECESSARY FLOOR SLAB DEMOLITION FOR THE INSTALLATION OF NEW FOUNDATIONS, PIPING OR CONDUITS.
19. THE CONTRACTOR SHALL USE A WET SAW FOR SLAB SAWING. NO JACK HAMMERS WILL BE ALLOWED WITHOUT PRIOR APPROVAL FROM WAL-MART CONSTRUCTION MANAGER.
20. REMOVE EXISTING CERAMIC TILE/QUARRY TILE AT AREAS TO RECEIVE NEW FLOOR FINISH. PREPARE CONCRETE SUBSTRATE. CEMENT GROUT INFILL DEPRESSED AREAS, FLUSH AND LEVEL FOR NEW FLOOR FINISH FOR SMOOTH TRANSITION TO ADJACENT FLOOR AREAS.
21. SAW CUT AND REMOVE EXISTING SIDEWALKS, PAVING, CURBS, STAIRS AND FENCING AS REQUIRED FOR THE CONSTRUCTION OF THE EXPANSION. REMOVE ALL EXISTING PAVING AND FLATWORK WHICH IS NOT REQUIRED FOR CONSTRUCTION OF THE NEW ADDITION AND/OR SHOWN TO BE REMOVED. COMPLETELY REPLACE ALL PAVING REMOVED. COMPLETE JOB TO MATCH EXISTING PAVING MATERIAL IN THICKNESS AND REINFORCEMENT.
22. REMOVE EXISTING FLUSH-MOUNTED PVC CORNICE. REMOVE ALL MATERIAL FROM WALL SURFACES. REPAIR WHERE DAMAGED. FASTENERS WILL BE REMOVED. REFINISH WAL-MART MATERIAL. REPLACE EXISTING BUILDING SUPPORTED CORNICE AT INTERSECTION OF SHINGLE ROOF.
23. WHEN CUTTING SHINGLE EXISTING CMU WALL FOR A NEW OPENING, REMOVE EXISTING 8" BELOW FINISH FLOOR AND A MINIMUM OF 1' 4" WIDER THAN SAWING FOR INSTALLATION OF NEW LINTEL AND TOOTH-IN NEW CMU EACH JAMB.
24. THE CONTRACTOR SHALL COORDINATE WITH THE WAL-MART CONSTRUCTION MANAGER IF PHASING IS REQUIRED FOR CONSTRUCTING THE VESTIBULE ENTRY AREA. PROVIDE TEMPORARY ENTRANCE IN THE DIRECTION INDICATED. PROVIDE NEW VESTIBULE IS COMPLETE. REMOVE TEMPORARY ENTRANCE AND REQUIRED INSTALL NEW MASONRY INFILL FOR A SMOOTH FINISH.
25. WHEN RELOCATION OF TRASH COMPACTORS, BALERS, ATM AREAS AND ATM UNITS ARE REQUIRED, COORDINATE THE SCHEDULE WITH THE WAL-MART CONSTRUCTION MANAGER AND WITH THE WAL-MART REPRESENTATIVES.

WAL-MART CONTACTS:

COMPACTOR/BALERS: WAL-MART RECYCLING (479) 273-8175 AND/OR (479) 273-6171

ATM UNIT: WAL-MART FINANCE DEPARTMENT (479) 273-4528

CONTACT THE WAL-MART FINANCE DEPARTMENT A MINIMUM OF TWO WEEKS PRIOR TO THE MOVE OR DISCONNECTION OF AN ATM UNIT.

AT COMMENCEMENT OF PROJECT, COORDINATE WITH WAL-MART TO ENSURE ADEQUATE TIME IS PROVIDED FOR THE RELOCATION OF THESE ITEMS.

26. WHERE EXISTING FIRE ROD EXISTS, REMOVE FROM ROOF PARAPET OR WALL. PATCH, REPAIR AND REFINISH SURFACES TO MATCH EXISTING UNLESS NOTED OTHERWISE ON DRAWINGS.
27. AT EXISTING EXTERIOR WALLS TO REMAIN, REMOVE EXISTING ANCHOR DEVICES AT EXISTING SIGNAGE WHICH IS TO BE REMOVED. PATCH WALLS AND FINISH SURFACE TO MATCH EXISTING.
28. PROTECT ALL WATER PIPING AT AREAS OF DEMOLITION, EXPANSION AND REMODEL. WHERE EXISTING PIPING IS SUBJECT TO FREEZING, PROTECT PIPING SO AS NOT TO FREEZE.

GENERAL FLOOR PLAN NOTES

REFER TO SHEET A1

1. ALL DIMENSIONS ARE TO FACE OF CMU, OR STUD UNLESS NOTED OTHERWISE.
2. ALL INTERIOR DIMENSIONS ARE ORIGINAL FOR MERCHANDISE PLANNING.
3. NEW DRESSING ROOMS SHALL BE PROVIDED AND INSTALLED BY WAL-MART.
4. THE CONTRACTOR SHALL PROVIDE A SMOOTH TRANSITION BETWEEN THE EXISTING AND NEW FLOOR SURFACE ELEVATIONS. VERIFICATION OF EXISTING ELEVATIONS IS CRITICAL PRIOR TO THE PLACEMENT OF THE NEW SLAB.
5. IF THE EXISTING STORE IS FIRE RATED OR IS RETROFITTED TO BECOME FIRE RATED, ALL EXISTING FLOOR, CEILING, AND WALL SURFACES SHALL BE TENTED TO ACHIEVE A ONE HOUR FIRE RATED ASSEMBLY. TENT ALL NEW LIGHT FIXTURES, AS REQUIRED.
6. CLEAN, PATCH AND REPAIR EXISTING WALL SURFACES SCHEDULED TO BE REFINISHED. ALL EXISTING GYPSUM BOARD SURFACES, WHICH ARE DAMAGED IN ANY WAY SHALL BE REPAIRED PRIOR TO THE APPLICATION OF SCHEDULED WALL FINISH. REMOVE WALL STANDARDS PRIOR TO REFINISHING EXISTING WALLS. ANCHORS IN EXISTING WALLS WHICH STORE FIXTURES AND STANDARDS ARE REMOVED. COORDINATE REPAIR AND REFINISHING WALLS WITH THE WAL-MART CONSTRUCTION MANAGER. WORK AT EXISTING WALLS SHALL BE DONE IN PHASES. PHASING AS DIRECTED BY WAL-MART CONSTRUCTION MANAGER/STORE MANAGER.
7. PROVIDE VERTICAL GYPSUM BOARD CONTROL JOINTS (JGC #093) IN A PARTITIONS AT 30' 0" OC (MAXIMUM) AND AT EACH DOOR JAMB OPENING.
8. PAINT ALL NEW AND EXISTING EXPOSED COLUMNS AS SCHEDULED(EXCEPT AT STOCKROOMS). CONTRACTOR SHALL INSTALL NEW WOOD BASE AROUND GYPSUM BOARD PURRED COLUMNS (IF APPLICABLE). REFER TO SPECIFICATIONS FOR INTERIOR PAINT COLOR SCHEDULE.
9. INFILL ALL CMU MASONRY UNITS WITH INSULATION AT ALL NEW EXTERIOR WALLS.
10. NOT USED
11. WAL-MART WILL PROVIDE RESILIENT FLOORING, CERAMIC TILE, AND PLANK FLOORING AND ADHESIVE FOR INSTALLATION BY CONTRACTOR. REVIEW WITH WAL-MART CARPET/TILE PLAN PRIOR TO INSTALLATION.
   A. INSTALL RESILIENT FLOORING AND/OR PVC PLANK FLOORING AT NEW AND EXISTING BUILDING SLAB.
   B. REMOVE RUBBER TILE, QUARRY TILE, AND CARPET IN AREAS TO RECEIVE NEW CERAMIC TILE FLOORING AND/OR PVC PLANK FLOORING.
   C. CONTRACTOR SHALL PREPARE SUBSTRATE FOR INSTALLATION OF NEW RESILIENT FLOORING, CERAMIC AND PLANK FLOORING TILE.
   D. CONTRACTOR SHALL DETERMINE QUANTITY OF VCT AND PVC PLANK FLOORING, FEATURE TILE AND ADHESIVE. NOTIFY WAL-MART OF QUANTITY REQUIRED. REFER TO SHEET FD1. REFER TO RESILIENT AND PVC PLANK FLOORING SPECIFICATIONS.
12. THE CONTRACTOR SHALL CLEAN AND WAX NEW RESILIENT AND PVC PLANK FLOORING LOCATED WITHIN THE ARCH EXPANSION PORTION OF THE PROJECT. THE CONTRACTOR SHALL ALSO WAX NEW RESILIENT AND PVC PLANK FLOORING AT THE GROCERY AREA REGARDLESS OF LOCATION. ALL NEW FLOOR SHALL BE PROTECTED FROM SCRATCHING, MARKING, STAINING, ETC. DURING CONSTRUCTION AND WAX TILE OR PVC PLANK THAT IS DAMAGED BY CONSTRUCTION AND DOES NOT APPEAR IN NEW CONDITION AT THE TIME OF INSPECTION WILL BE REMOVED BY THE GENERAL CONTRACTOR AT HIS EXPENSE. INSTALL RESILIENT TRANSITION STRIP WHERE FLOOR TILE ABUTS EXPOSED CONCRETE FLOOR.
13. THE CARPET WILL BE FURNISHED BY WAL-MART AND INSTALLED BY CONTRACTOR. REFER TO CHERRYVILLE NOTES. THE CONTRACTOR SHALL PREPARE FOR ALL AREAS UNDER CARPET TO BE LEVEL, AND PREPARE FOR CARPET. CONTRACTOR SHALL REMOVE EXISTING CARPET.
14. INSTALL SHEARTIN NEW XPSRIB INTERIOR CORNER BEAD AT HIGH COLUMNS JOINTS. REFER TO SPECIFICATIONS.
15. CLEAN ALL EXISTING HVAC GRILLES WHICH REMAIN. REPLACE CONTRACT COMPLETION.
16. REMOVE ALL ACCESSIBLE AREAS OF CEILING TILES. RE-INSTALL SALES AREA AS APPROPRIATE. COORDINATE ALL WORK PERFORMED IN THE EXISTING SALES AREA WITH THE WAL-MART CONSTRUCTION MANAGER AND STORE MANAGER. REPAIR AND REPLACE DAMAGED OR MISSING COMPONENTS. REPLACE DISCOLORED, DIRTY AND BROKEN CEILING PANELS.
17. ALL INTERIOR PARTITIONS SHALL BE METAL STUDS AT 24" OC UNLESS NOTED OTHERWISE. PROVIDE FIRESTOPS IN STUD WALLS AS REQUIRED.
18. WIRE GUARDS ARE REQUIRED FOR ANY WORK PERFORMED IN THE EXISTING SALES AREA PRIOR TO POSSESSION. THIS INCLUDES, BUT NOT LIMITED TO, REPAIRING FLOORING, DRILLING WORK, PAINTING, ELECTRICAL CHANGES AND PHASES OF WORK WHICH INTERFERES WITH THE STORE OPERATIONS.
19. THE GC PROVIDES FIRE SPRINKLER SYSTEM IN EXPANSION AREA ONLY. FUTURE. REFER TO FIRE SUPPRESSION SPECIFICATIONS.
20. MOVABLE SHELVING UNITS ARE NOT DESIGNED FOR STORAGE OF GOODS ABOVE EACH UNIT TO BE 78" WIDE. THE MAXIMUM HEIGHT BETWEEN SHELVES IS 6'0". LOCATED IN THE SHOPPING AREA FOR THE RELEASE OF SMOKE AND HEAT FOR ACTIVATION OF THE SPRINKLER SYSTEM. REFER TO STRUCTURAL FOR THICKNESS AND CONDITIONS UNDER ALL NEW WORK. PROVIDE HIGH-TEMPERATURE SPRINKLERS. ANY ITEMS THAT BACK CONFLICT WITH THE SPRINKLER SYSTEM MUST BE REMOVED BY THE CONTRACTOR. ITEMS THAT WAL-MART TAKES POSSESSION OF REMAIN. ELECTRICAL DRAWINGS FOR ALL MOVABLE SHELVING UNITS ARE TO BE FURNISHED AND INSTALLED BY WAL-MART.

SYMBOLS LEGEND

- 10'12" — KEYNOTE INDICATOR
- 3301 — EQUIPMENT INDICATOR
- P3 — COLOR INDICATOR
- 8-A3 — FULL AND PARTIAL SECTION INDICATOR
- 15 A5 — EXTERIOR AND INTERIOR ELEVATION INDICATOR
- SALES 100 — ROOM NAME AND NUMBER
- A8 — WALL INDICATOR
- 101 A 2 — DOOR INDICATOR
- M — WINDOW INDICATOR
- TV — TV MONITOR: REFER TO 2&4-A0.7 FOR MOUNTING DETAIL. VERIFY EXACT LOCATION WITH LOSS PREVENTION MANAGER
- W = WALL MOUNTED
- A — COLUMN LINE IND CATOR
- 100'-0" FF FL — HEIGHT ELEVATION INDICATOR
- 100'-0" — PLAN ELEVATION INDICATOR
- 5 A2 — ENLARGED DETAIL INDICATOR

DETAIL NAME
SCALE SCALE SCALE
INTERNAL INFORMATION ONLY

PARTITION LEGEND

DETAIL:

PLAN:

LETTER INDICATES PARTITION TYPE
REF PLANS
HEIGHT-INCHES
GAUGE

NUMBER INDICATES STUD SIZE
INDICATES STUD HEIGHT TO BOTTOM OF ROOF DECK

1 = 1 5/8" METAL
2 = 2 1/2" METAL
3 = 3 5/8" METAL
5 = 6" METAL
6 = 8" CMU
12 = 12" CMU

- 1 HOUR RATED GYPSUM BOARD ASSEMBLY CMU WALL ASSEMBLY
- NEW CMU WALL
- NEW METAL STUD WALL
- ACOUSTICAL INSULATION FULL WALL THICKNESS
- CHAIN LINK FENCE
- INDICATES 4' 0" HIGH PLASTIC LAMINATE WAINSCOT UNO
- INDICATES 4'-0" HIGH PLYWOOD WAINSCOT ON 2x8 BASE UNO
- INDICATES 2' 0" HIGH PLYWOOD WAINSCOT ON 2x8 BASE UNO
- EXISTING CONSTRUCTION TO REMAIN
- EXISTING CONSTRUCTION TO BE DEMO

RESTROOM SYMBOLS

WALL MOUNTED SIGNAGE TO BE LOCATED ON LATCH SIDE OF DOOR, CLEAR OF DOOR SWING. MOUNT AT 60" CENTER-LINE 6" SIGN FROM FLOOR.

MEN

RAISED 1/32" UPPERCASE LETTERING

HEIGHT OF LETTERING 5/8" MIN. TO 2" MAX.

60"

CORRESPONDING GRADE II BRAILLE

CHECK-OUT IDENTIFICATION

THE INTERNATIONAL SYMBOL OF ACCESSIBILITY IS THE STANDARD USED TO IDENTIFY FACILITIES AND AREAS READILY TO AND ACCESSIBLE BY PHYSICALLY DISABLED PERSONS AS SET FORTH IN THE 2003 IBC AS SPECIFIED AND REQUIRED IN THIS SECTION.

2. THE INTERNATIONAL SYMBOL OF ACCESSIBILITY SHALL CONSIST OF A WHITE PICTOGRAM ON A BLUE BACKGROUND. THE BLUE SHALL BE EQUAL TO COLOR NO. 15090 IN FEDERAL STANDARD 595B.

LETTERS AND NUMBERS ON SIGNS SHALL HAVE A WIDTH-TO-HEIGHT RATIO OF BETWEEN 3:5 AND 1:1, AND A STROKE WIDTH TO HEIGHT RATIO OF BETWEEN 1:5 AND 1:10.

A. INSTALL RESILIENT NUMBERS AND/OR PVC PLANK FLOORING AT NEW AND EXISTING BUILDING SLAB.
B. REMOVE RUBBER TILE, QUARRY TILE, AND CARPET IN AREAS TO RECEIVE NEW CERAMIC TILE FLOORING AND/OR PVC PLANK FLOORING.
C. CONTRACTOR SHALL PREPARE SUBSTRATE FOR INSTALLATION OF NEW RESILIENT FLOORING, CERAMIC AND PLANK FLOORING TILE.

CHARACTERS AND SYMBOLS SHALL CONTRAST WITH THE BACKGROUND.

WHEN RAISED CHARACTERS OR SYMBOLS ARE REQUIRED, THEY SHALL CONFORM TO THE FOLLOWING:
A. LETTERS AND NUMBERS ON SIGNS SHALL BE RAISED 1/32" MINIMUM AND SHALL BE SANS SERIF UPPERCASE CHARACTERS AND ACCOMPANIED BY GRADE 2 BRAILLE.
B. RAISED CHARACTERS OR PICTOGRAMS SHALL BE A MINIMUM OF 5/8" HIGH.
C. PICTOGRAM SYMBOL SIGNS (PICTOGRAMS) SHALL BE ACCOMPANIED BY THE EQUIVALENT VERBAL DESCRIPTION AND ACCOMPANIED BY BRAILLE. THE PICTOGRAM DIMENSION OF THE PICTOGRAM SHALL BE A MINIMUM OF 6" IN HEIGHT.

CONTRACTED GRADE II BRAILLE SHALL BE USED WHEREVER BRAILLE SYMBOLS ARE SPECIFICALLY REQUIRED IN OTHER PORTIONS OF THESE REGULATIONS. DOTS SHALL BE 1/10" ON CENTER IN EACH CELL WITH 2/10" SPACE BETWEEN CELLS. DOTS SHALL BE RAISED A MINIMUM OF 1/40" ABOVE THE BACKGROUND.

8. WHEN PERMANENT IDENTIFICATION IS PROVIDED FOR ROOMS AND SPACES, RAISED LETTERS SHALL BE ACCOMPANIED BY BRAILLE. SIGNS SHALL BE INSTALLED ON THE LATCH SIDE OF THE DOOR. WHERE THERE IS NO WALL SPACE ON THE LATCH SIDE, INCLUDING DOUBLE LEAF DOORS, SIGNS SHALL BE PLACED ON THE NEAREST ADJACENT WALL. PREFERABLY ON THE RIGHT. MOUNTING HEIGHT SHALL BE 60" ABOVE THE FINISHED FLOOR TO THE CENTERLINE OF THE SIGN. MOUNTING LOCATION SHALL BE DETERMINED SO THAT A PERSON MAY APPROACH WITHIN 3" OF THE SIGNAGE WITHOUT ENCOUNTERING PROTRUDING OBJECTS OR STAN